A PRACTICAL PATH TO O'NEILL COLONIES

Bootstrapping Lunar Industry from a Superconducting Cable and an Asteroid

Jon Smirl

Independent Researcher

jonsmirl@gmail.com

March 2026

Concept Paper

Abstract

Building O'Neill-class space habitats requires gigawatt-scale power and millions of tons of steel—neither available off Earth. This paper presents a gravity power plant that provides both from a single system. Three insights drive the design: (1) a space elevator used exclusively for *descent*, not ascent, is a power plant—rocks fall, electricity comes out; (2) a superconducting cable (REBCO, $YBa_2Cu_3O_7$) with carbon-fiber radiating fins converts the kinetic energy of falling cargo to persistent current via Lenz's law—the cable is simultaneously the generator, the battery, and the transmission line, with zero moving parts; (3) the power scales sublinearly with cable thickness—10× the power requires only 3.2× the cable mass, reaching 10+ GW with existing materials.

The complete cycle: M-type asteroid iron-nickel is crushed, resistance-sintered into magnetized half-rings, and clamped around the cable. The rings descend 62,000 km from Earth-Moon L1 to the lunar surface via flux pinning and Lenz's law braking,

generating 1.2 GW at baseline throughput. The rock—already metallic—is smelted into structural steel using the power it just generated. A surface mass driver launches finished steel to lunar orbit for habitat construction. One 600 m asteroid provides the full material for a 2 km rotating habitat: a radiation-shielded, impact-proof city for 200,000 people with 31 km^2 of $1g$ interior.

For Mars delivery, the mass driver launches steel sections at the departing habitat—each catch simultaneously builds the structure and provides propulsion (no propellant expended). Autonomous robots complete the interior during the 10-year transit. At the destination, the habitat drops a superconducting cable to the surface, mines a local moon for fuel, and replicates the gravity plant—a self-propagating industrial architecture.

At $40B for 1.2 GW (vs. $50–70B for equivalent lunar nuclear power, which requires enriched uranium launched from Earth and 100,000 m^2 of waste-heat radiators), this system provides a credible path from a Starship launch contract to a self-sustaining industrial civilization across the solar system.

Contents

1 The O'Neill Bootstrapping Problem **5**

1.1 Solar . . . 5

1.2 Nuclear . . . 6

1.3 Gravitational Potential Energy . . . 6

1.4 Three Key Insights . . . 7

2 System Overview **8**

2.1 Mass and Energy Flow . . . 9

3 The Cable **9**

3.1 Why the Moon, Not Earth . . . 9

3.2 Structure . . . 9

3.3 The Two-Wire Circuit . . . 10

3.3.1 Superconductor selection: why REBCO . . . 11

3.3.2 Why the return wire does not interfere with braking . . . 12

3.3.3 Voltage in the cable . . . 12

3.4 The Helical Winding: Track, Brake, and Generator . . . 12

3.5 Energy Storage (SMES at L1) . . . 13

3.5.1 Why both braking mechanisms feed the same loop . . . 14

3.5.2 Experimental precedent: superconducting flux pumps . . . 14

3.6 Thermal Budget: Braking Heat vs. Radiative Cooling . . . 15

3.6.1 Where the braking energy goes . . . 15

3.6.2 Radiative cooling capacity . . . 15

3.6.3 Thermal balance . . . 16

3.6.4 Local thermal diffusion . . . 16

3.6.5 Filament diameter specification . . . 16

3.6.6 Design rule . . . 17

3.7 Solar Thermal Budget: Radiating Fins . . . 17

3.7.1 The bare-cable problem . . . 17

3.7.2 The radiating fin solution . . . 18

3.7.3 Fin efficiency . . . 18

3.7.4 Fundamental scaling law . . . 19

3.7.5 Temperature predictions . . . 19

3.7.6 Self-blocking and view factor correction . . . 20

3.7.7 Ring compatibility . . . 20
3.7.8 Fin mass . . . 20
3.7.9 Micrometeorite shielding (dual use) . . . 21
3.8 Quench Protection . . . 21
3.8.1 Detection . . . 21
3.8.2 Energy dump . . . 21
3.8.3 Recovery . . . 22
3.8.4 Quench protection mass . . . 22
3.9 Cable Tension and the Counterweight . . . 23
3.10 Manufacturing: Integrated PLD Tape Line at L1 . . . 23
3.10.1 Continuous PLD tape manufacturing . . . 23
3.10.2 Two-tape staggered start . . . 24
3.10.3 PLD line specifications . . . 24
3.10.4 Joints . . . 25
3.10.5 Gen 1 vs. Gen 2+ material sourcing . . . 25

4 Two-Asteroid Architecture **25**
4.1 Tether Asteroid (Permanent) . . . 25
4.1.1 Station-Keeping from Ring Departure Momentum . . . 26
4.2 Mining Asteroid (Consumable) . . . 26

5 The Iron Ring **27**
5.1 Ring Fabrication . . . 27
5.2 Ring Parameters . . . 29
5.3 Self-Locking via Flux Pinning . . . 29
5.4 Structural Integrity During Braking . . . 30
5.5 Ring Release . . . 30
5.6 Ring Spin (Deliberate) . . . 30
5.7 Coriolis Lateral Force . . . 31

6 Descent Physics **31**
6.1 The Terminal Velocity Problem . . . 31
6.2 Variable-Helix Solution . . . 31
6.3 L1 Departure . . . 32
6.4 Descent Profile . . . 32

7 Surface Operations and Power Delivery **32**
7.1 Cable Endpoint and Ring Disposal . . . 32
7.2 Microwave Power Beaming . . . 33
7.3 Lunar Surface Station . . . 33

8 Mass Driver: Steel Export **34**
8.1 Sled Design . . . 34
8.2 Launch Velocity . . . 34
8.3 Fault Tolerance . . . 34

9 Power Extraction **35**

10 Energy Budget **35**
10.1 Generation and Internal Consumption . . . 35
10.2 Power Utilization . . . 36

11 Cost and Schedule **37**
11.1 Cost Estimate . . . 37
11.2 Schedule . . . 38
11.3 Comparison to Lunar Nuclear . . . 38

12 Risk Assessment **39**
12.1 Cable Severance (Critical) . . . 39
12.2 Ring Jam at Release Point (Moderate) . . . 39
12.3 Mass Driver Failure (Low Impact) . . . 39
12.4 Mining Asteroid Exhaustion (Planned) . . . 39

13 Development Roadmap **40**
13.1 Phase 0: Ground Demonstrations (Years 0–3, $500M) . . . 40
13.1.1 Open physics questions for Phase 0 resolution . . . 40
13.2 Phase 1: LEO Experiments (Years 3–6, $2B) . . . 41
13.3 Phase 2: Asteroid Technology (Years 3–10, $3B) . . . 42
13.4 Phase 3: Lunar Surface (Years 6–10, $2B) . . . 42
13.5 Phase 4: Full-Scale Construction (Years 10–21, $25B) . . . 43
13.6 Development Timeline Summary . . . 43

14 Scaling to Higher Power **43**

15 From Power Plant to Colony Builder **44**
15.1 The 1.2 GW Baseline . . . 44
15.2 First Habitat: Construction at the Tether . . . 44
15.3 Phase 2: Surface Infrastructure and Mars Habitats . . . 45
15.4 The 10 GW Colony Builder . . . 45
15.4.1 Habitat sizing: spin loads and wall design . . . 46
15.4.2 Radiation and impact protection . . . 48
15.4.3 Mass budget per habitat . . . 48
15.4.4 The reference habitat: 2 km diameter . . . 49
15.4.5 One asteroid, one city . . . 49
15.4.6 Spin-up sequence . . . 50
15.4.7 Lunar regolith: completing the bill of materials . . . 50
15.4.8 Habitat power and lighting . . . 51
15.4.9 Water, nitrogen, and volatiles: C-type asteroids . . . 51
15.4.10 Complete bill of materials . . . 52
15.4.11 Lunar vicinity, not Earth orbit . . . 53
15.5 Why This Is the Only Practical Path . . . 53
15.6 The Uranium Argument . . . 54
15.7 A Shipyard for the Solar System . . . 54
15.7.1 Departure: construction steel as propulsion . . . 54
15.7.2 The 10-year slow transfer . . . 55
15.7.3 Arrival: flip the habitat, catch slingshot steel . . . 55
15.7.4 The complete Mars delivery sequence . . . 56
15.7.5 Mass budget from one 500 m asteroid . . . 57
15.7.6 No Mars infrastructure required . . . 57
15.7.7 The robot fleet . . . 57
15.7.8 Timeline: one million at Mars . . . 58
15.7.9 Self-replicating architecture . . . 59

16 Conclusion **62**

1. The O'Neill Bootstrapping Problem

In 1976, Gerard O'Neill proposed building large rotating space habitats from asteroid and lunar material, housing millions of people in Earth-like environments. The engineering is straightforward: an O'Neill cylinder (Island Three) is a 32 km steel tube, spinning for gravity. The problem has never been the *design*—it has been the *bootstrapping*. Building one requires ∼50 million tons of processed steel and ∼10 GW of continuous power sustained for years. Every path to these numbers hits a wall:

- **Launch from Earth:** even a 2 km habitat requires ∼400 million tons of steel and shielding. At $100/kg: $40 trillion. No.
- **Mine lunar regolith:** The regolith is 20% iron oxide. Reducing oxide to metal costs ∼15,000 MJ/ton—requiring GW-scale power that doesn't exist on the Moon (see below).
- **Mine asteroids in microgravity:** Smelting without gravity doesn't work. No slag separation, no convection, no casting. You cannot run a steel mill in zero-g.
- **Build solar panels first:** 10 GW of solar requires 50 km^2 of panels. Made from what? You need the metal first. Chicken-and-egg.

Every path requires industrial infrastructure to build industrial infrastructure. This paper presents an architecture that breaks the loop: a *gravity power plant* that generates GW-scale electricity from descending asteroid rock, where the rock that generates the power is already metallic (M-type asteroid iron-nickel, requiring no oxide reduction) and becomes the smelter feedstock after generating electricity. The only Earth-supplied components are a cable and an initial carrier fleet. Everything else—power, material, and products—comes from gravity and asteroids.

Before presenting the design, this section reviews why conventional power technologies cannot provide the energy that O'Neill-scale industry demands.

1.1 Solar

Lunar solar provides ∼1,360 W/m^2 during the 14-day sunlit period, but nothing during the 14-day night. A 1 GW average output requires either ∼7 km^2 of panels with 14-day energy storage (∼1,200 GWh in batteries or thermal mass), or placement at a permanently illuminated polar peak—of which only a handful exist, none large enough for gigawatt-scale installations. Solar does not scale to continuous industrial power on the Moon.

1.2 Nuclear

Nuclear fission provides continuous power independent of sunlight. However, on the Moon it faces three problems absent on Earth:

(i) **Heat rejection.** On Earth, nuclear plants reject waste heat to rivers, oceans, or cooling towers. On the Moon, the only mechanism is thermal radiation into space. A 100 MW_e reactor at 30% thermal efficiency must radiate ~230 MW_{th} of waste heat. By Stefan-Boltzmann ($P = \sigma A T^4$), radiators at 800 K require ~10,000 m^2 of surface area *per reactor*. For 1 GW (ten reactors): 100,000 m^2 of radiator panels—fragile, heavy structures that must be assembled in vacuum.

(ii) **Fuel logistics.** A 1 GW plant consumes ~1.5 tons of enriched uranium per year. This fuel must be manufactured on Earth, packaged for spaceflight, and launched. At current Starship reliability (~99%), a 20-year fuel supply requires ~30 launches carrying nuclear material. The statistical expectation is at least one launch failure with enriched uranium aboard—a contamination event that would halt the entire program. Public opposition to launching kilograms of plutonium in RTGs is already intense; launching *tons* of enriched uranium would face overwhelming political resistance.

(iii) **Development cost.** No space nuclear reactor above 5 kW_e has ever operated (Soviet TOPAZ, 1987). NASA's Kilopower demonstration produced 1 kW_e. Scaling to 100 MW_e is a factor of 100,000 with no intermediate steps. Development cost for the first unit: \$15–25B. Manufacturing ten units for a 1 GW plant: \$20–30B. Total realistic cost for 1 GW lunar nuclear: \$50–70B.

1.3 Gravitational Potential Energy

This paper proposes a third option: converting the gravitational potential energy of asteroid material into electricity. Material at Earth-Moon L1 has ~2,700 kJ/kg of potential energy relative to the lunar surface. A superconducting cable from L1 to the surface captures this energy as persistent current via Lenz's law braking—with zero resistive loss. At 1,600 tons/hour throughput, the captured power is ~1.2 GW.

The "fuel" is asteroid rock. It is delivered by redirecting near-Earth asteroids to the L1 vicinity—a capability already demonstrated in principle by NASA's DART mission. The rock descends the cable, generates electricity, and accumulates at the surface as waste (or feedstock for optional smelting). No uranium, no radiators, no moving parts in the generator.

1.4 Three Key Insights

This paper rests on three observations, each departing from the assumptions of prior work:

1. **Down, not up.** Every space elevator proposal in the literature is about *ascent*—lifting cargo from a gravity well. This paper inverts the concept: the value is in the *descent*. The elevator is a drain, not a pump. Rocks fall down; electricity comes out. Everything else in the design—the mass driver for steel export, the passive terminal, the construction-as-propulsion delivery of habitats—follows from this inversion.

2. **The superconductor is the generator.** Previous superconducting space proposals used the superconductor for levitation or structural support. Here, the REBCO wire converts kinetic energy to persistent current via Lenz's law braking—the cable is the generator, with zero moving parts and zero resistive loss. The same wire that brakes the iron ring stores the energy (SMES) and delivers it to the grid. Generator, battery, and transmission line in one component.

3. **Scale.** The system produces 10 GW with existing materials (carbon fiber and REBCO superconducting tape). No fusion. No exotic physics. Just a thicker cable. Every previous space power proposal tops out at 1–100 MW—enough for a research station, not a civilization. 10 GW is what separates an outpost from an industrial economy.

   Critically, the scaling is *sublinear*. Power scales with the cable's cross-sectional area (which determines carrier throughput), while cable mass scales with cross-sectional area times length. Since the length is fixed (62,000 km), 10× the power requires only $\sqrt{10}\times$ the diameter = 3.2× the cable mass. No other space power technology has this property: nuclear scales linearly (10× power = 10× reactors = 10× cost), and solar scales linearly (10× power = 10× panels). The gravity plant scales by *cross-section*:

Power	Cable diameter	Cable mass	Cost
1.2 GW	22 mm	150,000 t	$40B
10 GW	45 mm	220,000 t	$80B
100 GW	100 mm	690,000 t	$180B

   100 GW—the power output of a medium-sized country—for $180B and one cable. The nuclear equivalent (1,000 reactors with 10 million m^2 of radiators) is not physically constructable.

2. System Overview

The gravity power plant is an **orbital power station**. Power is generated in space, steel is smelted in space, and habitats are built in space. The lunar surface serves only two functions: receiving beamed microwave power, and hosting a mass driver for habitat departure. No cable touches the ground.

The complete system consists of five components:

1. **Cable** (62,000 km): a single continuous carbon fiber core from the tether asteroid through L1 to 1 km above the lunar surface. Above L1 (5,000 km): bare CF structural rope. Below L1 (57,000 km): REBCO superconducting tape (CORC architecture) with 24 radiating fins. The cable is free-hanging—no surface anchor. Iron rings descend the cable via flux pinning, generating power through Lenz's law braking.

2. **Tether asteroid** (5 million tons, ∼75 m diameter M-type): redirected to 5,000 km above L1. Counterweight that keeps the cable taut. Never mined.

3. **L1 station**: clamped to the cable at L1, where effective gravity is zero. Houses the SMES (persistent current energy storage), ring foundry (crusher + sintering presses), centrifuge smelter (rotating arm, $1g$ at the crucible for slag separation and casting), and a 1.8 km microwave phased-array transmitter for beaming power to the surface. The station bears no cable tension—forces pass through the continuous CF core.

4. **Mining asteroid** (300+ million tons, ∼600 m diameter M-type, consumable): a separate asteroid in a nearby but distinct orbit. Mined for material, ferried to the L1 station. Half is sintered into iron rings for power generation (descends the cable); half is smelted directly at L1 for orbital steel construction. Total consumption: ∼26 Mt/year. Replaced every ∼10 years.

5. **Iron rings** (expendable): asteroid iron-nickel crushed, packed into half-ring molds, and resistance-sintered with a 10 kA current pulse that simultaneously welds and magnetizes the iron. Two halves clamped around the cable; flux pinning ($\mu_r > 5{,}000$) self-locks them in place. The rock *is* the carrier. Rings that have generated power are spent fuel—they fall from the cable endpoint and are either collected for surface smelting (Moon) or discarded (Mars, Jupiter).

2.1 Mass and Energy Flow

Step	Physics
Iron-nickel crushed, sintered into half-rings (10 kA pulse)	Resistance welding
Half-rings clamped around cable, flux pinning engages	EM (passive)
Ring descends cable (62,000 km, ∼12 hrs)	Gravity (passive)
Lenz's law braking captures energy in SMES at L1	EM (passive)
Ring arrives at ∼0 m/s, REBCO ends 1 km above surface	Gravity (passive)
Ring falls from cable endpoint (spent fuel, discarded or collected)	Gravity (passive)
Power beamed to surface via 1.8 km microwave array	Microwave (active)
Surface: smelter processes collected iron, mass driver launches steel	EM sled (active)

The system is a one-way flow: asteroid rock descends, electricity comes out at L1, steel is smelted in orbit, and power is beamed to the surface. **Nothing returns to L1.** No cable touches the ground. The surface receives only microwave energy and falling iron.

3. The Cable

3.1 Why the Moon, Not Earth

A terrestrial space elevator to GEO requires specific strength >50 MYuri, achievable only with carbon nanotubes (TRL 2). The lunar cable to L1 requires only ∼2.5 MYuri, achievable with commercial carbon fiber (TRL 9). The taper ratio (thickest-to-thinnest cross-section) is 2.3× for the Moon versus $> 10^{50}$ for Earth. The lunar cable is buildable with existing materials.

3.2 Structure

The cable is a composite of carbon fiber (structural), two REBCO superconducting tape stacks (electrical), and 24 radiating fins (thermal management):

Parameter	Value
Total length	62,000 km per cable (5,000 bare CF to L1 + 57,000 REBCO to Moon)
Base diameter (surface)	22 mm
L1 diameter (thickest)	30 mm (taper ratio 2.3×)
Carbon fiber tensile strength	7 GPa
Design stress	3.5 GPa (50% safety factor)
Superconductor	REBCO ($YBa_2Cu_3O_7$), $T_c = 93$ K
Tape architecture	1–3 µm REBCO on 50 µm Hastelloy substrate (no silver sheath)
Conductor stacks	2 × 50-tape stacks (1 helical + 1 axial return) for 10 kA
Radiating fins	24 pitch-CF fins at 15° spacing, 120 mm × 100 µm
Fin coating	OSR silver-Teflon ($\alpha_s = 0.01$, $\varepsilon_{\mathrm{IR}} = 0.90$)
Total cable mass	∼150,000 tons (36,000 CF + 75,000 REBCO tape + 39,000 fins)

3.3 The Two-Wire Circuit

Persistent current requires a closed superconducting loop—current cannot be stored in an isolated straight wire. The cable contains two REBCO superconducting tape stacks forming a single loop:

(i) **Helical tape stack:** wound around the carbon fiber core at variable pitch. This is the working conductor—it brakes the carriers, generates EMF, and couples magnetically to the carrier's Halbach tube. Each stack contains ∼50 layers of REBCO tape (1–3 µm REBCO on 50 µm Hastelloy substrate), providing 10 kA capacity at 70 K in 0.2 T applied field with 1.5× safety margin. **No silver sheath**—REBCO uses a thin-film architecture (pulsed laser deposition on metal substrate), eliminating the $30B silver cost of Bi-2223 powder-in-tube tape.

(ii) **Axial return tape stack:** runs straight along the cable core. Same 50-tape stack carrying the return current. Does not interact meaningfully with the ring (see below).

Total REBCO conductor mass: ∼62,000 tons (dominated by the Hastelloy substrate, not the superconductor—the REBCO layer itself is only ∼19 tons). Combined with the carbon fiber structure (∼30,000 tons) and 24 radiating fins (∼32,000 tons), total cable mass is ∼150,000 tons.

The complete circuit is a single closed superconducting loop within the one cable: SMES at L1 → helical tape stack down (57,000 km) → jumper at cable endpoint → axial tape stack up (57,000 km) → SMES. The cable carries 10 kA persistent current. Power is

extracted at the L1 station via a persistent current switch and beamed to the surface by microwave (Section 7.2). Each tape within a stack is manufactured as a single jointless piece by continuous PLD as the cable pays out from the tether asteroid (Section 3.10).

3.3.1 Superconductor selection: why REBCO

Three superconductor candidates were evaluated. The selection is driven by three requirements unique to a 62,000 km space cable: (1) surviving solar thermal loads, (2) affordability at scale, and (3) manufacturability from off-Earth materials for self-replication.

MgB_2 ($T_c = 39$ K): Cheapest and easiest to fabricate as wire. Excellent for off-Earth production—magnesium is 5% of lunar regolith, and boron (5 ppm) is extractable with sufficient processing energy. However, MgB_2 cannot survive the solar thermal environment. A bare 20 mm cable in direct sunlight equilibrates at ∼166 K with the best OSR coatings. Even with 48 radiating fins, the worst-case temperature is ∼58 K—still 19 K above T_c. The required $\alpha_s/\varepsilon < 0.0003$ is physically unattainable. **MgB_2 is ruled out by solar thermal physics.**

Bi-2223 ($T_c = 110$ K): Best thermal margin. With 12 fins, worst-case temperature is 81 K (29 K margin). However, Bi-2223 uses powder-in-tube manufacturing with a silver matrix sheath comprising ∼40% of tape mass. For 78,000 tons of tape: 31,000 tons of silver at ∼\$965/kg = \$30B—more than half the project budget. Silver and bismuth are also essentially absent off-Earth (Bi: 10 ppb in lunar regolith; Ag: trace), making Bi-2223 permanently Earth-dependent. Additionally, Bi-2223 sintering requires 840°C in controlled O_2 atmosphere—incompatible with vacuum manufacturing at L1. **Bi-2223 is ruled out by silver cost and Earth dependency.**

REBCO ($YBa_2Cu_3O_7$, $T_c = 93$ K): The selected superconductor. REBCO uses thin-film deposition (pulsed laser deposition, PLD) of a 1–3 µm superconducting layer on a Hastelloy substrate—**no silver sheath**. Key advantages:

- **Cost:** Hastelloy substrate at ∼\$30/kg vs. silver at ∼\$965/kg. Conductor cost: ∼\$3B vs. \$35B for Bi-2223.
- **Thermal:** With 24 radiating fins, worst-case temperature is 69 K (24 K margin below $T_c = 93$ K). With coating degraded to $\alpha_s = 0.02$: 82 K (11 K margin). See Section 3.7.
- **Vacuum manufacturing:** PLD is natively a vacuum process—L1 provides free vacuum. The cable's REBCO tape is deposited continuously at L1 as it is wound, producing jointless conductors of unlimited length (Section 3.10).
- **Off-Earth materials:** Every element in REBCO tape is available from M-type asteroid smelting residues. The thin-film architecture requires only ∼19 tons of REBCO (Y, Ba, Cu, O) on ∼62,000 tons of Hastelloy substrate (Ni, Cr, Fe, Mo). At 120 Mt/year

asteroid throughput: yttrium (0.1 ppm) yields 12 tons/year (need 2.5 tons); barium (0.01 ppm) yields 1.2 tons/year (need 7.7 tons, accumulated during the 6-year winding period); copper (200 ppm) yields 24,000 tons/year; nickel, chromium, iron, and molybdenum are abundant in the metallic phase. **REBCO is the only high-T_c superconductor whose cable can be manufactured entirely from asteroid materials** (Section 15.7.9).

- **Production scaling:** Global REBCO production exceeds 5,000 km/year (2025) and is scaling rapidly, driven by fusion reactor demand (Commonwealth Fusion Systems, tokamak magnets). By the 2040s construction timeframe, production capacity and cost reduction will far exceed current levels.

3.3.2 Why the return wire does not interfere with braking

The axial return wire carries 10 kA and creates a circumferential magnetic field:

$$B_{\text{return}} = \frac{\mu_0 I}{2\pi r} = \frac{4\pi \times 10^{-7} \times 10{,}000}{2\pi \times 0.15} = 0.013 \text{ T} \tag{1}$$

at the iron ring bore (150 mm from the cable center). The ring's magnetization is approximately radial (from the sintering pulse). A radially magnetized ring in a circumferential field experiences *tangential* forces that cancel by symmetry around the circumference. **Net axial force from the return wire on the ring: zero.**

The return wire's field (0.013 T) is also small compared to the Halbach interior field (0.2 T)—a 6.7% perturbation that does not significantly affect the helical wire's braking behavior.

3.3.3 Voltage in the cable

In a superconductor, $V = IR = 0$. There is no voltage drop along either wire. The 1 GW of power is at 10 kA × 100 kV, but the 100 kV appears only at the *surface power converter* (where the persistent current switch forces current through the resistive load). Along the 62,000 km cable, the voltage between the two wires is zero in steady state. Each carrier contributes ∼125 V of local EMF over its 3 m length—125 V across a 10 mm vacuum gap, far below vacuum breakdown (>30 kV at 10 mm). No arcing risk. No high-voltage insulation needed along the cable.

3.4 The Helical Winding: Track, Brake, and Generator

The helical REBCO tape wound around the carbon fiber core creates two functions:

(i) **Braking track with variable profile:** the carrier's permanent magnets moving past the helical superconductor experience a changing magnetic flux. The superconductor's screening currents oppose the flux change (Lenz's law), creating a braking force. The winding machine at L1 varies the helix pitch during manufacturing: open pitch (100 mm) in the upper cable gives light braking and fast cruise; dense pitch (3 mm) in the bottom 50 km gives heavy braking, decelerating the carrier from cruise speed to ∼2 m/s at the terminal. The braking profile is permanently "programmed" into the cable geometry.

(ii) **Linear generator:** each turn of the helix acts as a generator coil. As the ring moves past, the changing flux through each turn induces EMF in the loop. For a ring of height $L_r = 1$ m at speed v, passing N helix turns with circumferential conductor length ℓ:

$$\text{EMF per ring} = N \times B \times \ell \times v = N \times 0.2 \times 0.063 \times v \tag{2}$$

At 10 turns/m in the cruise zone: $N = 30$ turns per ring, EMF $= 0.378 \times v$. At 333 turns/m in the braking zone: $N = 1{,}000$, EMF $= 12.6 \times v$.

With ∼1,920 rings distributed along the cable at a time-weighted average speed of ∼330 m/s:

$$\text{Total EMF} = \sum_{i=1}^{800} 0.378 \times v_i \approx 100{,}000 \text{ V} = 100 \text{ kV} \tag{3}$$

At loop current $I = 10$ kA:

$$P = \text{EMF} \times I = 100 \text{ kV} \times 10 \text{ kA} = 1 \text{ GW} \quad \checkmark \tag{4}$$

3.5 Energy Storage (SMES at L1)

The energy storage is a superconducting solenoid at the L1 station—not distributed in the cable. The cable is a *transmission line and generator*; the SMES coil is the *battery*.

A dedicated REBCO solenoid (100 m diameter, 1,000 turns) at the L1 station stores energy as persistent loop current in zero gravity. At operating current $I = 10$ kA:

$$E = \frac{1}{2} L_{\text{SMES}} I^2 \tag{5}$$

The SMES inductance is sized for the desired buffer depth. At $L = 100$ H: $E = 5$ GJ (5 seconds at 1.2 GW). At $L = 1{,}000$ H: $E = 50$ GJ (50 seconds). The buffer smooths the power delivery from the 1,920 rings continuously charging the loop.

Energy extraction uses a persistent current switch and DC-to-microwave converter at the L1 station, feeding the 1.8 km phased-array transmitter (Section 7.2). Standard SMES technology deployed commercially for grid stabilization.

3.5.1 Why both braking mechanisms feed the same loop

Two distinct forces brake the ring: the generator effect ($F = NB\ell I$, speed-independent, from EMF induction in the helix) and flux pinning ($F \propto v$, speed-dependent, from vortex drag in the Type II superconductor). At the surface, the generator provides ∼11% of the total braking force and flux pinning provides ∼89%. This is a force partition, **not an energy partition.**

Both mechanisms deliver energy to the *same loop current*. In a superconducting loop, total enclosed flux is conserved ($V = IR = 0 \Rightarrow d\Phi_{\text{total}}/dt = 0$). When the ring's magnetization pushes flux vortices *into* the wire (flux pinning), that flux is no longer enclosed by the loop—the enclosed flux decreases. To conserve total flux, the loop current must increase: $L\,dI = -d\Phi_{\text{external}}$. The energy goes into $\frac{1}{2}LI^2$.

The generator effect drives current increase via EMF (Faraday's law). Flux pinning drives current increase via flux conservation (vortex entry). Both result in the same outcome: higher loop current, more stored energy in the SMES. The only loss is hysteresis heat from vortex motion through pinning sites (∼0.30 J per ring per 1 m section, a fraction of 3×10^{-9} of the braking energy).

Essentially 100% of the gravitational PE is captured as extractable persistent current. There is no "missing" energy, no cable heating, and no need to oversize the system for partial capture.

3.5.2 Experimental precedent: superconducting flux pumps

The electromagnetic mechanism described above is not novel physics—it is a *traveling-wave flux pump* scaled to 62,000 km. Coombs [1] demonstrated that moving a magnetic field across an HTS tape drives DC persistent current without electrical contact and without interrupting superconductivity, achieving >96% efficiency during pumping and 98% in maintenance mode. Flux pumps have been demonstrated at currents up to 100 kA [1]—the cable operates at 10 kA, well within demonstrated capability. Emetere [2] demonstrated YBCO-based linear generators using permanent magnets moving past HTS coils, confirming the Faraday's law EMF equations used in this paper and identifying AC loss from flux flow as the primary thermal challenge—the same conclusion reached in Section 3.7.

Each descending iron ring is the equivalent of the rotating permanent magnet in a flux

pump: its field sweeps across the helical REBCO tape, inducing the "dynamic voltage" effect that drives persistent current in the closed superconducting loop. The helical geometry converts the ring's linear motion into the traveling-wave pattern required for unidirectional current pumping. The Phase 0 ground demonstration (Section 13.1) is therefore a scaled traveling-wave flux pump experiment, not a novel physics test.

3.6 Thermal Budget: Braking Heat vs. Radiative Cooling

A critical feasibility question: does the braking phase generate enough heat to quench the REBCO superconductor? The answer requires distinguishing between *stored energy* (persistent current) and *dissipated energy* (AC losses).

3.6.1 Where the braking energy goes

A 10-ton iron ring entering the braking zone at 100 m/s carries ∼50 MJ of kinetic energy (plus gravitational PE). Electromagnetic braking converts this energy into persistent current in the superconducting wire—*stored energy*, not heat. In a perfect superconductor, this conversion is lossless. The cable acts as a SMES battery: the current increases, the stored magnetic energy increases, and no heat is generated.

The only heat comes from *AC losses*: hysteresis from flux vortex motion through pinning sites in the Type II superconductor. For REBCO tape with fine filaments ($d_f = 20$ µm), the hysteresis loss per flux cycle is:

$$W_h = \frac{4}{3}\Delta B \cdot J_c \cdot d_f \approx 5{,}333 \text{ J/m}^3 \text{ per cycle} \tag{6}$$

where $\Delta B \approx 0.5$ T (iron ring bore field) and $J_c = 10^9$ A/m^2 (REBCO at 70 K). Each ring passage constitutes one flux cycle. For the REBCO volume under a 1 m ring (∼19 cm^3):

$$Q_{\text{heat}} = 5{,}333 \times 1.9 \times 10^{-5} = 0.10 \text{ J per ring passage} \tag{7}$$

This is 0.10 J of heat versus ∼50 MJ of stored energy—a loss fraction of 2×10^{-9}. Essentially all braking energy goes into persistent current.

3.6.2 Radiative cooling capacity

In vacuum, the finned cable sheds heat by thermal radiation. At 80 K (13 K below the worst-case solar equilibrium of ∼69 K from Section 3.7, providing margin for AC losses):

$$P_{\text{rad}} = \varepsilon\sigma \times (\text{effective radiating area}) \times T^4 \approx 0.9 \times 5.67 \times 10^{-8} \times 0.71 \times 80^4 \approx 149 \text{ mW/m} \tag{8}$$

3.6.3 Thermal balance

At any fixed point on the cable, one ring passes every 27 seconds, depositing 0.10 J over a 1 m length:

$$\dot{q}_{\text{avg}} = \frac{0.10}{1 \times 27} = 3.7 \text{ mW/m} \tag{9}$$

The AC heat input (3.7 mW/m) is 40× below the radiative cooling capacity at 80 K (149 mW/m). Braking heat is negligible compared to both the solar thermal load (Section 3.7) and the cable's cooling capacity. **AC losses do not constrain the thermal design.**

3.6.4 Local thermal diffusion

The 0.30 J of heat is generated inside the REBCO layer and must diffuse into the Hastelloy substrate before the filament overheats locally. The thermal diffusion time across a 20 µm filament:

$$t_{\text{diffuse}} = \frac{d_f^2}{\alpha} = \frac{(20 \times 10^{-6})^2}{3.85 \times 10^{-4}} \approx 1 \text{ ns} \tag{10}$$

The ring passage takes ∼3 ms at cruise speed. Heat leaves the filament millions of times faster than the ring passes. No local hotspot can form.

3.6.5 Filament diameter specification

The thermal constraint sets a manufacturing specification for the REBCO tape. The maximum radiated energy per ring passage at 100 K is $P_{\text{rad}} \times 54$ s = 13 J/m—far above any AC loss. The hysteresis loss per meter scales linearly with filament diameter d_f:

d_f (µm)	Q_h (J/m)	Margin	Status
10	0.050	5.2×	Commercial (development)
15	0.075	3.4×	Commercial (HyperTech)
20	0.101	2.6×	Commercial (standard)
30	0.151	1.7×	Commercial (Columbus SC)
50	0.251	1.0×	Marginal

Maximum allowable filament diameter: $d_f < 52$ µm. Commercial REBCO tape from SuperPower, AMSC, and Fujikura provides conductors meeting this specification. **This is a procurement specification, not a research problem.** The required wire is commercially available today.

3.6.6 Design rule

The transition zone (200 km, moderate helix) must reduce the ring speed to $\leq$100 m/s before entry to the dense-helix braking section. At 100 m/s, the initial deceleration is $\sim 8g$ but the AC heat generation is only 10 W during the 30 ms passage—safely within the cable's thermal budget. Validation requires a single laboratory measurement: AC loss in REBCO tape at 0.2 T, 33 Hz, 70 K, using standard superconductor characterization equipment.

3.7 Solar Thermal Budget: Radiating Fins

AC losses from braking are negligible ($\sim$1.85 mW/m). The dominant thermal challenge is **solar radiation**: a 62,000 km cable in open space absorbs up to 272 mW/m even with the best coatings. This section proves that 24 carbon-fiber radiating fins keep the REBCO cable ($T_c = 93$ K) below T_c from all solar angles.

3.7.1 The bare-cable problem

A bare 20 mm cylindrical cable in direct sunlight at 1 AU absorbs:

$$P_{\text{abs}} = \alpha_s \cdot d \cdot S = \alpha_s \times 0.020 \times 1{,}361 \text{ W/m} \tag{11}$$

where α_s is the solar absorptivity and $S = 1{,}361$ W/m^2 is the solar flux. The cable radiates:

$$P_{\text{rad}} = \varepsilon \cdot \pi d \cdot \sigma_{\text{SB}} \cdot T^4 \tag{12}$$

At equilibrium:

$$T^4 = \frac{\alpha_s}{\varepsilon} \cdot \frac{S}{\pi \sigma_{\text{SB}}} \tag{13}$$

For the best available optical solar reflector (OSR) coating, silver-Teflon ($\alpha_s = 0.08$, $\varepsilon = 0.80$):

$$T = \left(\frac{0.08}{0.80} \times \frac{1{,}361}{\pi \times 5.67 \times 10^{-8}} \right)^{1/4} = 166 \text{ K}$$

This exceeds both MgB_2 ($T_c = 39$ K) and YBCO ($T_c = 93$ K). For MgB_2, the required $\alpha_s/\varepsilon < 0.0003$—no known material achieves this. Even YBCO requires $\alpha_s/\varepsilon < 0.010$, at the ragged edge of laboratory coatings and infeasible over a 62,000 km cable. **No passive surface treatment on a bare 20 mm cable can reach 93 K in direct sunlight.**

3.7.2 The radiating fin solution

The cable's radiative cooling capacity scales as the emitting surface area, while its solar absorption scales as the projected cross-section (diameter). Adding radial fins increases the emitting area without proportionally increasing the solar cross-section, because the fins are thin and present minimal edge area to the Sun.

Design: 24 longitudinal fins of pitch-based carbon fiber, 100 µm thick, 120 mm radial height, bonded to the cable surface at 15° intervals. All surfaces coated with OSR ($\alpha_s \approx 0.01$, $\varepsilon \approx 0.90$).

Why carbon fiber, not aluminum: Aluminum (conductivity $\sigma = 3.77 \times 10^7$ S/m) inside the ring's 0.5–1.0 T bore field would generate eddy currents as the ring passes:

$$F_{\text{eddy}} = \sigma B^2 v t \cdot A_{\text{fin}} \sim 720 \text{ N per ring (aluminum)} \tag{14}$$

This would destroy the descent profile and waste more energy than the plant generates. Pitch-based carbon fiber ($\sigma = 5 \times 10^4$ S/m) has 500× lower conductivity:

$$F_{\text{eddy}} \approx 0.3 \text{ N per ring (carbon fiber)} = 0.15\% \text{ of braking force} \tag{15}$$

Negligible drag. Average eddy current heating over the full cable: <12 mW/m—four orders of magnitude below the solar load. Carbon fiber also provides thermal conductivity $k \approx 100$ W/(m·K) for efficient fin conduction.

3.7.3 Fin efficiency

A thin fin radiating to space develops a temperature gradient from base (warm) to tip (cool). The fin efficiency $\eta = \tanh(mL)/(mL)$ depends on:

$$m = \sqrt{\frac{2h_{\text{rad}}}{k \cdot t_{\text{fin}}}} \tag{16}$$

where $h_{\text{rad}} = 4\varepsilon\sigma_{\text{SB}}T^3$ is the linearized radiation heat transfer coefficient. At $T = 90$ K:

$$h_{\text{rad}} = 4 \times 0.9 \times 5.67 \times 10^{-8} \times 90^3 = 0.149 \text{ W/(m}^2\text{·K)}$$

For pitch carbon fiber ($k = 100$ W/(m·K)), fin thickness $t = 100$ µm, fin height $L = 120$ mm:

$$m = \sqrt{\frac{2 \times 0.149}{100 \times 10^{-4}}} = 5.46 \text{ m}^{-1}, \qquad mL = 5.46 \times 0.12 = 0.655$$

$$\eta = \frac{\tanh(0.655)}{0.655} = \frac{0.576}{0.655} = 0.879 \tag{17}$$

The fins are 88% efficient—the tip temperature is only modestly below the base temperature. This is adequate for the thermal budget below.

3.7.4 Fundamental scaling law

For N radial fins at equal angular spacing, the worst-case equilibrium temperature (Sun aligned with one fin) depends only on N, α_s, and ε—**not on fin height**. Both the solar cross-section and the convex-hull radiating perimeter scale linearly with fin height; the ratio is a constant. The exact result (derived from the solar silhouette geometry):

$$\boxed{T^4 = \frac{2\,\alpha_s \cos(\pi/N)}{\varepsilon \cdot N \cdot \sigma_{\mathrm{SB}}} \cdot S} \tag{18}$$

Proof. When the Sun is aligned with one fin (worst case), that fin is edge-on and presents negligible cross-section. The two adjacent fins (at angles $\pm 2\pi/N$ from the Sun) are visible and each projects a solar cross-section of $h\sin(2\pi/N)$. The total solar cross-section is $2h\sin(2\pi/N) = 4h\sin(\pi/N)\cos(\pi/N)$. The convex hull of N fins at radius h from center is a regular N-gon with perimeter $2Nh\sin(\pi/N)$. The equilibrium condition $\alpha_s \cdot (\text{solar cross-section}) \cdot S = \varepsilon \cdot (\text{convex hull}) \cdot \sigma_{\mathrm{SB}} \cdot T^4$ yields Equation 18 after cancellation of $h\sin(\pi/N)$. □

3.7.5 Temperature predictions

Fins (N)	T (α_s=0.01)	T (α_s=0.02)	T (α_s=0.03)	**REBCO (93 K)?**
4	99 K	117 K	131 K	no
8	89 K	105 K	118 K	fresh only
12	81 K	96 K	108 K	fresh only
24	**69 K**	**82 K**	**92 K**	**yes** ($\alpha_s \leq 0.03$)
36	62 K	74 K	83 K	yes (wide margin)

Design choice: 24 fins. With fresh OSR coating ($\alpha_s = 0.01$), the worst-case cable temperature is 69 K—24 K below $T_c = 93$ K. As the coating degrades to $\alpha_s = 0.02$ (typical after 7–10 years in the UV/particle environment), the temperature rises to 82 K with 11 K margin. Even at $\alpha_s = 0.03$ (severely degraded), the temperature is 92 K—1 K margin, requiring prompt recoating. Periodic recoating by a robotic maintenance carrier descending the cable (analogous to bridge painting) maintains $\alpha_s < 0.02$ indefinitely.

3.7.6 Self-blocking and view factor correction

The scaling law (Equation 18) assumes fins radiate from the convex hull only—self-blocking between adjacent fins is implicitly accounted for. For 24 fins at 15° spacing on a 130 mm radius, the convex hull (regular 24-gon) has perimeter 814 mm. The total physical fin surface (24 fins × 2 sides × 120 mm + cable circumference 63 mm = 5,823 mm) greatly exceeds the convex hull. The view factor to space is approximately:

$$\mathcal{F}_{\text{space}} = \frac{\text{convex hull}}{\text{total surface}} = \frac{814}{5{,}823} = 0.140$$

Multiplied by fin efficiency (0.879), the effective radiating area is $0.879 \times 0.140 \times 5{,}823 \approx 717$ mm/m. Since the convex hull perimeter (∼814 mm) already accounts for the geometric limit of radiation to space, and the scaling law uses the convex hull directly, the correction from finite fin efficiency reduces the effective radiation by ∼12%. This shifts the equilibrium temperatures upward by ∼3%:

$$T_{\text{corrected}} \approx T_{\text{ideal}} \times (1/0.879)^{1/4} = T_{\text{ideal}} \times 1.034$$

For the $N = 24$, $\alpha_s = 0.01$ case: $69 \times 1.034 = 71$ K. Still 22 K below $T_c = 93$ K. All entries in the table above include this correction factor.

3.7.7 Ring compatibility

The 24 fins extend from the cable surface (10 mm radius) to 130 mm radius. Iron rings (typical bore ∼150 mm radius) ride outside the fin tips with clearance. The ring's flux-pinning and braking interactions occur via the iron's high permeability ($\mu_r > 5{,}000$) coupling to the REBCO's screening currents. The fins are non-magnetic carbon fiber; they do not affect flux pinning, magnetic centering, or the variable-helix braking profile. Rings levitate over the fins without mechanical contact. The fins additionally serve as Whipple shields, protecting the cable from any fragments that might separate from a ring during descent.

3.7.8 Fin mass

Component	**Mass**
24 pitch-CF fins (120 mm × 100 µm × 62,000 km, $\rho = 1{,}800$ kg/m^3)	32,200 tons
OSR coating (silver-Teflon, <5 µm)	<400 tons
Total fin mass	**∼32,600 tons**

The fins add 26% to the non-fin cable mass and <3% to total system cost. The winding machine at L1 bonds the fins during cable manufacture—no additional infrastructure required.

3.7.9 Micrometeorite shielding (dual use)

The 24 fins serve as Whipple shield elements. A micrometeorite approaching from any direction must penetrate at least one 100 µm carbon fiber fin before reaching the superconducting cable core. The fin absorbs the kinetic energy, vaporizes locally, and the debris cloud decelerates before reaching the cable. This supplements (not replaces) the sacrificial outer sheath described in Section 12, but provides 24-fold angular coverage with zero additional mass.

3.8 Quench Protection

If a section of cable does transition to the resistive state (quench)—from a micrometeorite strike, localized damage, or an anomalous heat event—the 10 kA persistent current flowing through the newly resistive section would generate I^2R heating sufficient to vaporize the wire in milliseconds. Unprotected quench is catastrophic. The cable requires a quench protection system, standard in every superconducting magnet installation.

3.8.1 Detection

Quench propagation in REBCO is slow (∼1–10 m/s) compared to the speed of light in the cable. A resistive section develops a voltage $V = IR$ that is detectable within microseconds by distributed voltage sensors along the cable. The detection threshold is set below the level that would cause thermal damage.

3.8.2 Energy dump

Upon quench detection, the cable's stored energy ($\frac{1}{2}LI^2 = 2.5$ GJ at 10 kA) must be extracted before it dissipates in the quench zone. Two mechanisms operate simultaneously:

(i) **Dump resistors at the L1 station:** the persistent current switch opens (forced resistive transition), routing current through external dump resistors. At $V_{\text{dump}} =$ 1,000 V: the current decays from 10 kA with time constant $\tau = L/R = 50/0.1 = 500$ s. The 2.5 GJ dissipates as heat in the dump resistors over ∼8 minutes. The dump resistors are massive steel blocks or water-cooled banks—standard power engineering.

(ii) **Distributed quench heaters:** resistive heater strips bonded to the cable at intervals (∼every 100 m in the braking section, every 10 km elsewhere) force the entire cable to

transition simultaneously. This spreads the stored energy over the full 62,000 km cable length instead of concentrating it in one spot. Energy per meter: $2.5 \times 10^9 / 62 \times 10^6 = 40$ J/m—easily absorbed by the cable's thermal mass without damage.

3.8.3 Recovery

After a quench, the cable cools radiatively back below T_c (∼hours to days depending on the energy deposited). The persistent current is lost and the SMES is empty—no power is available. The system restarts from the **emergency ring queue** (Section 5.1):

1. Cable cools below T_c. Flux pinning re-engages, holding the queued rings in place.
2. The first queued ring is released—a small battery-powered backup sled provides the departure push (or the residual effective gravity below L1 initiates a slow descent).
3. That ring descends, generating a trickle of persistent current in the REBCO loop.
4. The SMES begins to charge. The trickle powers a stronger push on the next queued ring.
5. Each successive ring builds more current, enabling faster departures.
6. Within hours the system bootstraps back to full operating current from the queue.

The queue is both the emergency power buffer (preventing shutdown during foundry outages) and the cold-start mechanism (restarting after a quench). Without the queue, a quench would require fabricating and loading new rings with zero power available—an unrecoverable failure without external rescue. No physical repair is needed unless the quench was caused by structural damage.

3.8.4 Quench protection mass

Component	**Mass**
Dump resistors (steel blocks, L1 station)	5,000 kg
Persistent current switch (heater + SC section)	50 kg
Distributed quench heaters (every 100 m in braking zone)	200 kg
Voltage sensors (distributed, fiber-optic)	100 kg
Control electronics	20 kg
Total quench protection	**∼5,400 kg**

All components are standard superconducting magnet technology scaled to the cable's parameters. The quench protection system ensures that a quench event loses the *stored energy* (requiring re-charging) but does not damage the *cable structure* (requiring repair or replacement).

3.9 Cable Tension and the Counterweight

A cable can only carry tension, never compression. The tether asteroid above L1 must pull the cable outward (away from the Moon) with sufficient force to keep the free-hanging cable taut against the weight of the cable and rings below L1.

Below L1, the 22 mm cable's own weight (∼1,010 kN) plus descending rings (∼630 kN) pull *inward*—a total of ∼1,640 kN. The tether asteroid above L1 must provide at least this much outward pull.

At 5,000 km above L1, the effective gravity (centrifugal minus lunar minus terrestrial) is $g_{\text{eff}} = 0.000408$ m/s^2 directed away from the Moon. A 5-million-ton asteroid (∼75 m diameter) at this position exerts:

$$F_{\text{up}} = 5 \times 10^9 \times 0.000408 = 2{,}040 \text{ kN} \tag{19}$$

This exceeds the inward pull by 24%, keeping the cable taut with adequate margin.

3.10 Manufacturing: Integrated PLD Tape Line at L1

The single cable is manufactured by an integrated PLD/CORC facility at the tether asteroid. The facility deposits REBCO tape onto Hastelloy substrate (via continuous PLD) and winds it into a CORC cable (Conductor on Round Core) around a continuous carbon fiber core—the same helical tape-on-round-former architecture used in commercial HTS cables (Advanced Conductor Technologies). Raw materials (Hastelloy ribbon, REBCO target rods, carbon fiber, fin stock) are delivered from Earth via Starship for the Gen 1 lunar cable.

The facility pays out cable *downward* from the tether asteroid. The first 5,000 km (asteroid to L1) is bare carbon fiber—just structural rope, no REBCO, no fins. At L1, the PLD line activates and begins depositing REBCO onto the CF core. From L1 downward (57,000 km), the cable is a full CORC superconductor with 24 radiating fins. The cable is always under tension from its own weight, hanging from the asteroid. One cable, one winding machine, no tangling, no construction sequencing.

3.10.1 Continuous PLD tape manufacturing

REBCO tape is manufactured by pulsed laser deposition (PLD)—a vacuum process. L1 provides free, unlimited vacuum. The tape line deposits REBCO onto Hastelloy ribbon as a continuous reel-to-reel process:

1. Hastelloy ribbon feeds from spool (or, for Gen 2+, from continuous casting of asteroid-refined alloy)

2. Buffer layers (CeO_2, MgO) deposited by sputtering in vacuum
3. REBCO layer (1–3 µm) deposited by PLD in a small O_2 partial-pressure enclosure (∼0.1 mbar, oxygen extracted from lunar regolith or asteroid oxides)
4. Thin copper cap layer deposited by sputtering
5. Finished tape feeds directly into the cable winding machine

The tape never exists as a separate spool—it flows from deposition to cable in one continuous operation. **Each conductor (helical and axial) is a single jointless piece of unlimited length.**

3.10.2 Two-tape staggered start

The circuit requires two tape stacks: one helical (64,550 km, accounting for helix path length) and one axial (62,000 km). The cable pays out downward from the tether asteroid, so the dense-helix braking zone (at the cable's lower end) (50 km of cable = 1,050 km of helical tape) is manufactured *first*. The manufacturing sequence:

1. **Day 0:** Start the helical PLD line. Buffer 1,050 km of helical tape (∼18 days).
2. **Day 18:** Start the axial PLD line and carbon fiber/fin winding. Begin cable payout.
3. **Days 18–36:** Feed buffered helical tape (dense helix, 3 mm pitch) while axial tape feeds at cable payout speed. Buffer is fully consumed as the braking zone completes.
4. **Day 36 onward:** Both PLD lines run at constant speed for the remaining 5.85 years. The helical line runs 4.1% faster than the axial line (helix path > straight path). The winding machine controls pitch by varying the ratio of cable payout to tape feed.

No speed changes after startup. No buffering after the initial 18 days. Two constant-speed PLD lines, one cable.

3.10.3 PLD line specifications

Parameter	Value
Helical tape production rate	2,530 m/hr (4.1% faster than axial)
Axial tape production rate	2,431 m/hr
PLD deposition zone	5 m, five 600 W excimer lasers in series
Total laser power	3 kW per line (from the 1 GW plant: negligible)
O_2 enclosure	∼0.1 mbar, 5 m length, recycled O_2
Cable payout (cruise zone)	20 m/min = 29 km/day
Cable payout (braking zone)	2.8 km/day (tape speed unchanged, denser winding)
Total winding time	2,150 days = 5.9 years

3.10.4 Joints

The single-cable circuit has exactly **three joints**: two where the helical and axial tape stacks connect to the SMES at the L1 station, and one at the cable endpoint jumper (where the helical tape loops back to the axial tape). The L1 joints are hand-crafted, tested, and accessible. The endpoint joint is made during manufacturing as the last step before the cable tip is released. The REBCO tape within each stack is jointless—manufactured as a single continuous piece by the PLD/CORC facility as the cable pays out. Compare to pre-fabricated tape launched from Earth: ∼500,000 joints (one every 500–1,000 m of tape), each a potential failure point and a source of resistive loss.

3.10.5 Gen 1 vs. Gen 2+ material sourcing

For the Gen 1 lunar cable, all raw materials are launched from Earth:

Material	**Mass (tons)**	**Source**
Hastelloy ribbon	62,000	Earth (Ni/Cr/Fe/Mo alloy)
REBCO targets (Y, Ba, Cu, O)	25	Earth
Carbon fiber	30,000	Earth
Pitch-CF fin stock	32,000	Earth
PLD/winding equipment	∼50	Earth
Total	**∼150,000**	∼850 Starship flights

For Gen 2+ cables (Mars and beyond), all materials are sourced from M-type asteroid smelting (Section 15.7.9). The PLD equipment is the only permanent Earth import—a one-time cost of ∼50 tons that replicates at every destination.

4. Two-Asteroid Architecture

Two asteroids serve distinct functions: one permanent tether (counterweight) and one consumable mining asteroid (feedstock).

4.1 Tether Asteroid (Permanent)

- Mass: ∼5 million tons (∼75 m diameter M-type)
- Position: 5,000 km above L1 (67,000 km from Moon center)
- Function: counterweight only—never mined, never disturbed

- Cable: the single continuous CF core passes through the asteroid; bare CF above L1, REBCO below
- Redirect time: 5–10 years with solar electric tug
- Station-keeping: provided by ring departure momentum from the L1 station (no ion drive—see below)

4.1.1 Station-Keeping from Ring Departure Momentum

The tether asteroid requires periodic station-keeping corrections to maintain its position above L1. A conventional solution (ion drives) is unsuitable: the exhaust plume would deposit propellant atoms on the superconducting cable, degrading its surface properties over years of operation.

Instead, station-keeping is a *free byproduct* of ring launches. Each 10-ton ring receives an electromagnetic departure push of ∼10 m/s to clear the L1 equilibrium region. By Newton's third law, each push delivers 100 kN·s of reaction momentum directed *away* from the Moon (outward). At 133 rings per hour:

$$F_{\text{avg}} = \frac{133 \times 10{,}000 \times 10}{3{,}600} = 3.7 \text{ kN} \tag{20}$$

The required station-keeping force is ∼1.6 kN—the ring departures provide 2.3× the requirement. The departure push velocity can be modulated to fine-tune the station-keeping force. No propellant. No plume. No cable contamination.

4.2 Mining Asteroid (Consumable)

- Mass: 300+ million tons (∼600 m diameter M-type)
- Position: separate orbit near L1, safe distance from cable
- Function: material source ("fuel" for the power plant)
- Material crushed at asteroid, ferried to tether station
- Sintered into iron rings, loaded onto Drop Cable
- Consumption rate: ∼26 million tons/year (14 Mt rings + 12 Mt orbital smelting)
- Lifetime: ∼10 years per asteroid (at 70% utilization); redirect a replacement every decade

The separation protects the cable from all mining operations. The ferry from mining asteroid to tether asteroid is a short transfer in the L1 vicinity—low delta-v, simple trajectories.

5. The Iron Ring

5.1 Ring Fabrication

The ring foundry is a rigid tube assembly positioned along ∼1 km of REBCO cable *below* the SMES at L1. Rings cannot pass over the SMES (they are magnetized rings riding a superconductor), so the foundry must be downstream—between the SMES and the Moon. Raw iron-nickel is ferried from the mining asteroid, delivered past the SMES via the bare CF tether section above, and distributed to each press.

The foundry is a rigid tube (>1.68 m inner bore) flux-pinned to the cable at a single anchor point at its upstream end. The cable floats freely through the tube's center bore; descent rings pass through unobstructed. Thirty presses mount in a **compact helix** around the tube over ∼100 m of length—each press at a different angular position and height, spiraling around the bore. This arrangement keeps lever arms short (100 m maximum to the anchor, not 1 km), allows a single ore delivery hopper at the top to feed all presses, and prevents placement arms from interfering with each other (each reaches the cable from a different clock position). The tube is **rigid**—hydraulic rams, robotic arms, and capacitor discharges all produce reaction forces (Newton's third law) that would drift a non-rigid assembly into the cable. The rigid tube absorbs all internal reaction forces and transmits them to the flux-pinned anchor, which holds position against the cable via non-contact magnetic levitation. The cable is never bumped.

Each press is a self-contained unit on the tube: crusher intake, hydraulic ram, capacitor bank, robotic placement arm. The fabrication sequence per ring:

(i) **Crush:** mechanical crusher reduces asteroid material to fist-sized chunks (∼5–10 cm).

(ii) **Mold:** chunks are packed into a split half-ring mold and hydraulically compressed.

(iii) **Sinter and magnetize:** a 10 kA current pulse through the packed bed simultaneously resistance-sinters the chunk contacts and magnetizes the iron. Total energy input: $I^2Rt \approx 5$ kJ for a typical packed-bed resistance of ∼5 mΩ. Contacts reach melting temperature locally (fusing the chunks) but the multi-ton half-ring's thermal mass absorbs the heat: bulk temperature rise <0.01 K. The ring leaves the mold at ambient

temperature—no cooling required. A 50-turn coil around the mold produces ∼2 T, driving the iron to saturation ($B_{\text{sat}} \approx 1.6$–$2.0$ T). Remanent field: 0.5–1.0 T.

(iv) **Clamp:** two sintered half-rings are placed around the cable at the press location. Flux pinning engages automatically, locking the halves together and centering the ring.

(v) **Queue:** the finished ring is held on the cable by flux pinning, stationary, below the foundry. Rings accumulate in a queue between the foundry and the departure sled. This queue serves as an **emergency buffer**: a 12-hour reserve (∼160 rings) ensures continuous power generation even if the foundry goes offline for repairs. Without the buffer, a foundry shutdown drains the SMES in 12 hours (the last ring falls off), killing power to the foundry itself—an unrecoverable shutdown. The buffer breaks this dependency.

(vi) **Departure push:** an electromagnetic sled at the bottom of the queue pushes one ring at a time, initiating its 12-hour descent.

Manufacturing time per half-ring: ∼1 minute (fill 30 s, compress 10 s, pulse 1 s, eject 10 s). Two halves per ring: 2 minutes per press. At full capacity, 30 parallel presses each produce one ring every 10 minutes—well below their maximum rate, with 6+ minutes idle per cycle for longer sintering, reduced wear, and simpler automation. **Any press can fail without affecting the system**—29 of 30 presses maintain 97% throughput. Presses are repaired independently while the others continue.

Incremental startup. The system does not require full capacity on day one. Presses are added over time as demand grows:

Presses	Power	Phase	Supports
1	∼50 MW	Commissioning	L1 station operations
5	∼200 MW	Early operations	L1 smelter, beam test
15	∼600 MW	Surface power	Rectenna, surface smelter
30	1.2 GW	Full baseline	Mass driver operational
30+ (larger rings)	10 GW	Colony builder	Habitat production

Each press is a self-contained unit clamped to the cable. Scaling up = clamp on another press. Scaling down = take one offline. **First power requires one press, one ring, one descent.** Everything else grows from there.

5.2 Ring Parameters

The ring mass is optimized for a balance of manufacturing rate (one ring every ∼27 seconds), structural integrity during $8g$ braking, manageable mold dimensions, and adequate flux-pinning coupling to the cable.

Parameter	Value
Inner radius	150 mm (clears cable + 24 fins at 130 mm with 20 mm gap)
Outer radius	840 mm (1.68 m outer diameter)
Height	1.0 m
Mass per ring	∼10,000 kg (porous sintered iron, ∼60% of solid density)
Ring bore field	0.5–1.0 T remanent + REBCO screening reinforcement
Inner surface area	$\pi \times 0.3 \times 1.0 = 0.94$ m^2 (flux pinning contact)
Throughput	1,600 t/hr = 160 rings/hour (one every 22 seconds)
Rings on cable	∼1,920 simultaneously (avg. spacing 39 km)
Manufacturing	5 parallel sintering presses, 2 min per ring

The helix pitch (programmed into the cable during winding) is designed for the 10-ton ring's magnetic coupling. Iron-nickel's high saturation field (∼1–1.6 T) provides strong coupling; the helix pitch is widened accordingly to maintain the desired 12-hour descent profile and ∼1,600 t/hr throughput.

5.3 Self-Locking via Flux Pinning

The ring is held on the cable by a single mechanism: **flux pinning between the magnetized iron and the Type II superconductor.** The iron's remanent field (0.5–1.0 T) creates flux vortices in the REBCO that are pinned at lattice defects. This provides:

(i) **Centering:** the ring levitates at a fixed radial gap (∼20 mm from the fin tips), self-correcting in all directions. Displacement creates a restoring force.

(ii) **Locking:** the two half-rings are pressed together by the inward-directed pinning force. As long as the cable is superconducting, the halves cannot separate—the same airplane-door principle as a pressurized cabin.

(iii) **Braking:** the ring's magnetic field moving past the REBCO helix induces screening currents that oppose the motion (Lenz's law). The braking force is proportional to speed, providing passive deceleration.

5.4 Structural Integrity During Braking

The dense-helix braking zone (50 km, 3 mm pitch) decelerates rings at up to $8g$. The spot-welded ring must survive this without disintegrating. Three factors ensure survival:

(i) **Distributed magnetic force:** the $8g$ braking force is not transmitted through the welds. Each iron chunk in the ring interacts directly with the cable's magnetic field via its own magnetization. The force acts on the *bulk iron*, not on the weld joints. Each 0.5 kg chunk experiences ∼40 N individually.

(ii) **Compressive loading:** flux pinning pulls the ring inward toward the cable, compressing the sintered assembly. The ring is under compression, not tension. Sintered materials are strong in compression.

(iii) **Weld margin:** a 10-ton ring contains ∼20,000 fist-sized chunks with ∼50,000 spot-weld contacts. At $8g$ total braking force (785 kN), each weld bears ∼16 N of shear from differential magnetic coupling. A single iron spot weld holds >100 N. Safety factor: >6×.

5.5 Ring Release

The REBCO superconductor ends at the cable's free-hanging endpoint, 1 km above the lunar surface. The ring arrives at ∼0 m/s (fully decelerated by the braking helix). When it crosses the REBCO endpoint, flux pinning vanishes. The two half-rings, no longer pressed together, separate under their own weight and fall 1 km to the surface (∼57 m/s impact in $\frac{1}{6}g$). A deflection coil offsets the impact 700 m from the cable (Section 7.1). No mechanical release mechanism—the superconductor's endpoint *is* the release.

5.6 Ring Spin (Deliberate)

The helical winding creates a rotating magnetic field pattern relative to a descending ring. Unlike the earlier carrier design (which locked rotation via precise Halbach flux pinning), the sintered iron ring's irregular field allows controlled slip against the helix pattern—functioning as an induction motor with high slip. The result is a slow spin of ∼20–50 rpm induced naturally by the descent.

This spin is a safety feature. At 20 rpm and 840 mm outer radius, centrifugal acceleration is ∼3.7 m/s^2—2.3× lunar gravity. Any chunk that breaks free from a disintegrating ring is flung radially outward, away from the cable, rather than falling onto the cable or fins below. The cable is self-protecting against its own cargo.

5.7 Coriolis Lateral Force

The descending ring experiences a Coriolis force perpendicular to the cable (tangential, in the Moon's orbital plane). At maximum descent speed (2,000 m/s) and ring mass 10,000 kg:

$$F_{\text{Coriolis}} = 2m\omega v = 2 \times 10{,}000 \times 2.66 \times 10^{-6} \times 2{,}000 = 106 \text{ N} \tag{21}$$

The flux pinning restoring force (>10 kN for a 10-ton magnetized iron ring with 0.94 m^2 of bore contact on a REBCO cable) exceeds the Coriolis force by a factor of >90. The ring stays centered with enormous margin.

6. Descent Physics

6.1 The Terminal Velocity Problem

With passive Lenz's law braking (force proportional to speed), the ring reaches a terminal velocity where braking force equals gravitational force:

$$v_{\text{term}}(h) = \frac{m \cdot g_{\text{eff}}(h)}{k} \tag{22}$$

where k is the braking coefficient (determined by the magnetic coupling geometry). Since g_{eff} is highest at the lunar surface (1.62 m/s^2) and near zero at L1, the ring naturally goes *fastest at the bottom*—exactly where it must be slowest.

6.2 Variable-Helix Solution

The cable's REBCO helix pitch varies along its length, creating a position-dependent braking coefficient:

Section	**Length**	**Helix pitch**	**Effect**
Upper cable	56,950 km	100 mm (open)	Light braking, fast cruise
Transition zone	200 km	30 mm → 3 mm	Increasing braking
Braking section	50 km	3 mm (dense)	Heavy braking, ∼8g initial decel

The braking force scales as the square of the helix density (more flux changes per meter = more screening current = more force). A 33× tighter helix gives ∼1,000× more braking force—sufficient to decelerate from cruise speed to 2 m/s over 50 km.

6.3 L1 Departure

Near L1, effective gravity is essentially zero ($g_{\text{eff}} < 10^{-5}$ m/s^2). A passive ring starting from rest would take years to build speed. The ring requires an initial electromagnetic push from the tether asteroid station—the only active element in the descent chain. Once the ring reaches ∼10 m/s and enters the region of appreciable gravity (∼1,000 km from L1), passive braking and gravity handle the remainder of the descent.

6.4 Descent Profile

Altitude (km)	g_{eff} (m/s^2)	Speed (m/s)	Elapsed time
57,000 (L1 departure)	∼0	10 (pushed)	0
50,000	0.001	∼50	∼3 hrs
20,000	0.010	∼200	∼8 hrs
5,000	0.108	∼700	∼10 hrs
1,000	0.654	∼1,200	∼11 hrs
250 (enter transition)	1.3	∼1,500	∼11.5 hrs
50 (enter braking)	1.54	∼100	∼12 hrs
0 (surface)	1.62	∼2	∼12.5 hrs

Total transit: ∼12 hours. The ring accelerates slowly near L1, reaches maximum speed in the lower cable where gravity is strongest, then decelerates rapidly in the 50 km braking section.

7. Surface Operations and Power Delivery

No cable touches the lunar surface. The gravity plant is an orbital facility; the surface receives only microwave energy and falling iron.

7.1 Cable Endpoint and Ring Disposal

The cable is free-hanging, with its lower endpoint 1 km above the sub-L1 point on the lunar surface. Rings arrive at ∼0 m/s, flux pinning vanishes (REBCO ends), and the half-rings separate and fall 1 km to the surface (∼57 m/s impact in $\frac{1}{6}g$). An electromagnetic deflection coil at the cable endpoint imparts a ∼20 m/s lateral kick to offset the impact 700 m from directly below the cable, keeping dust plumes away from the REBCO. Deflection power: ∼220 kW.

The helical winding induces slow rotation (∼20–50 rpm) on descending rings. Centrifugal force (3.7 m/s^2 at the rim, 2.3× lunar gravity) flings any debris from a disintegrating ring

outward, protecting the cable. Ring imbalance vibration and deflection kick reactions cause the free-hanging cable endpoint to wander in a ∼1–6 km radius pattern (16-day pendulum period), naturally distributing impacts across a wide area and providing inherent safety for surface vehicles.

Ring arrival rate: one every 22 seconds (160 rings/hour at 10 tons each).

7.2 Microwave Power Beaming

Power is extracted from the SMES at the L1 station and beamed to the lunar surface via a microwave phased array, eliminating the need for any physical cable to the ground.

Antenna sizing. For efficient microwave transmission over distance D at wavelength λ, the transmit and receive antenna diameters must satisfy:

$$d_t \times d_r \geq \lambda \times D \tag{23}$$

At 5.8 GHz ($\lambda = 0.052$ m) over 61,000 km (L1 to surface), with equal apertures: $d_t = d_r \approx$ **1.8 km diameter**.

Transmit array (at L1). A 1.8 km phased-array antenna at the L1 station—dipole elements on a lightweight wire-mesh frame in zero gravity. Mass: ∼7,500 tons (built from asteroid iron at L1). Electronically steerable (no mechanical pointing).

Rectenna (on the surface). A 1.8 km rectifying antenna—aluminum wire mesh on regolith. Mass: ∼1,200 tons. No moving parts, no cryogenics. Located >30 km from the sub-L1 impact zone.

Efficiency. End-to-end DC-to-DC: ∼70% (no atmospheric absorption on the Moon). At 1 GW transmitted: **700 MW delivered to the surface.** The 300 MW sidelobe loss radiates harmlessly into space.

7.3 Lunar Surface Station

The surface station sits >30 km from the sub-L1 impact zone, beneath the rectenna:

- **Rectenna** (1.8 km diameter): receives 700 MW
- **Smelter** (400 MW): processes iron collected from the impact zone
- **Mass driver** (50–120 MW): launches finished steel to lunar orbit for habitat construction and departure propulsion

- **Power distribution**: lunar base, habitats, manufacturing

Autonomous vehicles collect iron half-rings from the sweeping impact zone and deliver to the smelter. The pendulum sweep distributes impacts across a wide quarry; vehicles trail the moving drop point, working areas where impacts landed minutes to hours earlier. **The spent fuel of the power plant is the feedstock of the refinery.**

8. Mass Driver: Steel Export

The mass driver's single function: **launching finished steel products to lunar orbit for habitat construction and departure propulsion.** Powered by 50–120 MW of beamed microwave energy received at the surface rectenna.

8.1 Sled Design

Finished steel sections are loaded into non-magnetic cradles atop an electromagnetic sled:

(i) Steel product placed in sled cradle at track base

(ii) Sled accelerates at $200g$ up the mountainside (1.4 km track, 1.2 seconds)

(iii) At ∼2,330 m/s, the sled brakes hard

(iv) The payload continues ballistically

(v) Sled regeneratively brakes, returns to start

(vi) Payload flies to lunar orbit (∼8 hours), caught by habitat construction systems

8.2 Launch Velocity

The minimum velocity to reach L1 is 2,323 m/s (set by the gravitational PE of 2,697 kJ/kg). The launch velocity is tuned to ∼2,330 m/s for construction steel delivery, or higher for interplanetary trajectories.

8.3 Fault Tolerance

If the mass driver fails, the cable continues generating power and the L1 station continues smelting. Only the surface steel *export* rate is affected—the orbital power and smelting operations are independent.

9. Power Extraction

Energy from descending iron rings is stored as persistent current in the superconducting cable (SMES). Extraction to usable electricity uses standard technology from MRI and grid-scale SMES systems:

(i) **Persistent current switch:** a short section of superconductor with a resistive heater. Activating the heater makes this section resistive, breaking the superconducting loop and forcing current through the external load. Standard in every MRI magnet for 40+ years.

(ii) **Power converter:** DC-DC or DC-AC converter between the cable and loads. Controls extraction rate via voltage modulation: $P = V \times I$, $dI/dt = -V/L$.

(iii) **Control system:** monitors cable current, schedules charge (descent) and discharge (loads) cycles, keeps current within safe operating limits.

Hardware mass: ∼3 tons. All commercial technology.

10. Energy Budget

10.1 Generation and Internal Consumption

Income	**MW**
Descent braking (1,600 t/hr × 2.7 MJ/kg)	1,200
Orbital consumption (at L1)	
Ring production (crusher + sintering presses)	∼15
Centrifuge smelter (orbital steel production)	∼100
Mechanical mining (at asteroid)	∼50
Subtotal orbital	∼165
Microwave beam to surface	
Transmitted from L1 (1,035 MW × 70% = 725 MW delivered)	1,035
Surface allocation (from 725 MW received)	
Surface smelter (processes collected iron)	∼350
Mass driver (steel export to orbit)	∼100
Lunar base, habitats, manufacturing	∼100

The plant generates ∼1.2 GW gross from a 22 mm cable (21% more than the 20 mm baseline). Of this, 165 MW is consumed at L1 for orbital operations, and 1,035 MW is fed to the microwave transmitter, delivering ∼725 MW to the lunar surface at 70% beam efficiency. The 310 MW of beam loss radiates harmlessly into space. Surface margin: ∼175 MW above the 550 MW surface load.

10.2 Power Utilization

The power serves two locations simultaneously—the L1 orbital station (direct) and the lunar surface (beamed). Each consumer also provides a direct benefit to the generator:

Activity	**Power (MW)**	**Benefit to generator**
Mechanical mining (at asteroid)	∼50	Eliminates metal vapor; protects cable
Active cryocooling (surface junction)	∼20	Increases T_c margin during lunar day
Ring production (crusher + sintering at L1)	∼15	Automates 1,600 t/hr throughput
Induction smelting (at base)	∼400	Turns descent iron into exportable steel
Total industrial allocation	∼435	
Remaining surplus	∼425	Available for external loads

The plant simultaneously generates electricity, mines asteroid material, smelts metals, and exports products—all from a single energy source (gravitational PE). The smelter alone (400 MW) processes the plant's own waste rock into the lunar colony's primary export: iron, nickel, and platinum group metals worth billions of dollars per year. The "waste" of the power plant is the feedstock of the refinery.

The ∼425 MW surplus powers the lunar base: habitats, manufacturing, life support, mass driver launches of products to cislunar destinations, and future expansion.

11. Cost and Schedule

11.1 Cost Estimate

Item	**Cost ($B)**
Starship launches (850 flights × $10M)[1]	8.5
Carbon fiber (36,000 tons × $100/kg)	3.6
Hastelloy ribbon (75,000 tons × $30/kg)	2.3
REBCO targets + PLD/CORC equipment	1.0
Radiating fins (39,000 tons pitch-CF + OSR coating)	1.2
Winding machine + L1 station + centrifuge smelter	1.5
Microwave phased array (7,500 tons, built at L1)	0.5
Surface rectenna (1,200 tons)	0.1
Tether asteroid redirect (4.8 Mt, solar tug)	0.6
Mining asteroid redirect (120 Mt)	2.0
Surface base (terminal, mass driver)	2.5
Ring production equipment (crusher + press)	0.1
Mining equipment + ferry system	1.5
Development + LEO experiments	3.0
Mission operations (11 years construction)	2.0
Contingency (30%)	9.1
Total	**∼40**

[1] REBCO tape uses thin-film deposition (PLD) on a Hastelloy substrate—no silver sheath. The superconductor cost is dominated by the Hastelloy ribbon ($30/kg, Ni/Cr/Fe/Mo alloy) and the PLD deposition equipment, not by exotic materials. The REBCO layer itself is only ∼19 tons of $YBa_2Cu_3O_7$ for the entire cable. Global REBCO production exceeds 5,000 km/year (2025), driven by fusion reactor demand, with costs trending toward $5–10/m at scale. For the gravity plant, PLD is performed at L1 as an integrated part of cable manufacture, eliminating the tape transport and joining costs that dominate Earth-based production.

11.2 Schedule

Year	Milestone
0–2	Technology development, LEO experiments, build winding machine
0–1	NEA survey: identify tether and mining asteroid candidates
1	Launch solar electric tugs for asteroid redirects
2–3	Ship winding machine and first cable spools to L1
3	Tether asteroid arrives 5,000 km above L1
3–9	Continuous cable winding: 29 km/day, 102 Starship flights/year
9	Cable endpoint reaches 1 km above lunar surface; deploy L1 station
10	Commission: test iron rings, mass driver, power extraction
10	Mining asteroid arrives in L1 vicinity
11	Operations begin: first rings descend

Critical path: cable winding (5.9 years). Everything else—asteroid redirects, surface construction, ring production equipment—fits within the winding period.

11.3 Comparison to Lunar Nuclear

Parameter	Gravity Plant	Nuclear (1 GW)
Capital cost	\$40B	\$50–70B
Construction time	11 years	7–15 years
Fuel	Asteroid rock (free)	Enriched uranium (\$100M/yr)
Fuel launch risk	Carbon fiber (inert)	Enriched uranium (catastrophic)
Heat rejection	None	100,000 m^2 radiators
Moving parts (generator)	Zero	Pumps, turbines, rods
Technology readiness	TRL 2–3	TRL 2–3
Single point of failure	Cable (meteorite)	No
Scales to 10 GW	Thicker cable (∼\$120B)	10× everything (∼\$600B)

Both technologies are at TRL 2–3 for lunar-scale deployment. Neither has been built. The gravity plant is cheaper, has no fuel launch risk, no radiator problem, and scales sublinearly. Its vulnerability is the cable—a single 62,000 km structure that a micrometeorite could sever.

12. Risk Assessment

12.1 Cable Severance (Critical)

The cable is a single point of failure. Mitigation strategies:

- **Redundant strands:** the cable is wound from multiple parallel REBCO tape stacks and 12 carbon fiber tows. A single-strand break does not sever the cable.
- **Whipple shielding:** the 24 carbon-fiber radiating fins serve as distributed Whipple shields, absorbing micrometeorite kinetic energy before it reaches the superconducting core. Ring spin (20–50 rpm) flings debris from disintegrating rings outward, away from the cable.
- **Monitoring:** distributed fiber-optic strain sensors detect damage early, allowing pre-emptive repair.
- **Repair capability:** robotic repair units stationed along the cable can splice damaged sections.
- **Spare cable (future option):** manufacture and deploy a second cable as a backup. Not part of the baseline design; listed as a risk mitigation option if operational experience warrants the investment.

12.2 Ring Jam at Release Point (Moderate)

Ring release is passive—flux pinning vanishes when the superconductor ends. No mechanism to jam. If a ring fails to separate into halves, it drops as a single piece to the surface. The next ring arrives 22 seconds later to a clear cable endpoint.

12.3 Mass Driver Failure (Low Impact)

Iron rings continue to descend and fall from the cable endpoint. Descent and power generation are unaffected. Only surface steel export to orbit is interrupted. The iron continues to accumulate in the impact zone. Repair the mass driver, work through the backlog.

12.4 Mining Asteroid Exhaustion (Planned)

Consumption rate is known precisely ($\sim$12 Mt/yr). Begin redirecting a replacement asteroid 5 years before exhaustion. The tether asteroid is permanent and never consumed.

13. Development Roadmap

The gravity power plant is at TRL 2–3 overall. No fundamental physics barriers exist, but five subsystems require significant development before full-scale construction. The following roadmap retires risks in order of difficulty, with each phase building on the previous one.

13.1 Phase 0: Ground Demonstrations (Years 0–3, $500M)

Retire the three novel concepts on Earth before going to space:

(i) **Iron ring flux-pinning demo:** build a 100 m horizontal REBCO cable in a cryostat (77 K, liquid nitrogen). Fabricate resistance-sintered iron half-rings and clamp them around the cable. Demonstrate: flux pinning levitation, Lenz's law braking at 10–50 m/s, self-locking of halves, and passive release when the ring crosses the superconductor's endpoint. Measure braking coefficients, pinning forces, and ring dynamics. This is the single most important experiment—it validates the core concept.

(ii) **Variable helix braking:** wind the test cable with variable-pitch REBCO helix. Demonstrate that a ring decelerates passively from 50 m/s to ∼0 m/s over the dense-helix section. Verify structural integrity of sintered rings at $8g$ deceleration. Measure the braking profile and compare to theory.

(iii) **Resistance sintering:** validate the ring fabrication process—crush, compress, 10 kA pulse—at full scale. Measure weld strength, remanent magnetization, and structural survival at $8g$ on a shock table. Characterize the relationship between sintering parameters (current, pressure, chunk size) and ring quality.

(iv) **Mass driver sled:** build a 200 m electromagnetic sled track. Launch 1,000 kg steel payloads at 500 m/s ($50g$). Demonstrate sled regenerative braking and payload separation. Scale modeling validates the 1.4 km, 2,330 m/s lunar design.

13.1.1 Open physics questions for Phase 0 resolution

Several design assumptions require experimental validation during ground demonstrations:

(i) **Variable helix braking scaling law:** the paper assumes braking force scales as the square of helix density (i.e., $F \propto (\dot{\Phi})^2$). For a Type II superconductor in the mixed state, the force may scale linearly with $\dot{\Phi}$, not quadratically. If linear, the transition zone (200 km) may need to be significantly longer. The 100 m cryostat demo directly measures this scaling.

(ii) **Iron ring remanence stability:** sintered iron-nickel is a soft ferromagnet with low coercivity. During heavy braking ($8g$), the cable's screening currents create fields at the ring bore that may partially demagnetize the iron. The ground demo measures the actual remanent field before, during, and after high-speed braking to verify that flux-pinning coupling is maintained throughout the descent profile.

(iii) **Cable energy buffer:** at $I = 10$ kA and $L = 50$ H, the cable stores 2.5 GJ—only ∼2.5 seconds at 1 GW extraction. The system operates with ∼1,920 rings continuously braking (charging the cable), so the buffer is continuously replenished. But startup and quench recovery require operating at reduced power until the persistent current rebuilds. The control dynamics of charge/discharge cycling need simulation and test.

(iv) **Distributed quench heater mass:** the current estimate (200 kg for 6,200 heater units) is likely too low. Each unit requires a battery, activation circuit, and heater element surviving decades in space. A realistic estimate may be 5,000–10,000 kg (1–2 kg per unit). This does not affect feasibility but corrects the mass budget.

13.2 Phase 1: LEO Experiments (Years 3–6, $2B)

Validate space-specific subsystems in low Earth orbit:

(i) **Cable winding in microgravity:** deploy a winding machine on a free-flying platform. Wind 10 km of cable with variable helix pitch. Verify winding quality, epoxy cure, and spool changes in vacuum/microgravity. Duration: 6 months. This validates the 6-year L1 manufacturing campaign.

(ii) **Cable deployment dynamics:** deploy 100 km of cable from a spool. Measure libration, oscillation modes, and tension profile. Compare to models. Validates the 62,000 km deployment from L1.

(iii) **Iron ring on deployed cable:** attach a sintered iron ring to the deployed cable. Demonstrate descent under Earth's gravity gradient, Lenz's law braking, and energy capture as persistent current. First end-to-end demonstration of the power generation cycle.

(iv) **Superconductor thermal management:** validate the cable's thermal performance in the LEO thermal environment (eclipse cycling, solar heating). Verify the finned REBCO cable remains below $T_c = 93$ K with passive radiative cooling from the 24 carbon-fiber fins and OSR coating.

13.3 Phase 2: Asteroid Technology (Years 3–10, $3B)

Develop asteroid mining in parallel with cable technology:

(i) **Asteroid prospecting mission:** visit 2–3 candidate M-type NEAs. Characterize composition, structure, spin rate, and mechanical properties. Select tether and mining asteroid targets. Builds on Psyche mission data (launching 2023, arriving 2029).

(ii) **Asteroid mining demo:** land on a small M-type NEA (<50 m). Demonstrate three cutting/splitting techniques: solar concentrator melting, mechanical drilling with wedge-and-split, and controlled explosive fragmentation. Process 100 tons of material. Sinter into prototype iron rings. This is the hardest development task—scaling from 121 grams (OSIRIS-REx) to 100 tons.

(iii) **Asteroid redirect demo:** attach a solar electric tug to a 10 m boulder (from the mining demo) and redirect it to Earth-Moon L1. Demonstrate precise orbital placement. Validates the 75 m and 200 m redirects needed for the full system.

(iv) **Microgravity material handling:** develop robotic systems for processing 10-ton iron-nickel charges into sintered rings at the tether station. Test with the demo asteroid material. This is a novel industrial robotics problem—bulk solids handling in microgravity.

13.4 Phase 3: Lunar Surface (Years 6–10, $2B)

(i) **Site survey:** high-resolution survey of the sub-Earth region (0°N, 0°E) from lunar orbit. Identify a suitable location for the surface rectenna (>30 km from the sub-L1 impact zone) and characterize terrain for the mass driver track.

(ii) **Surface construction demo:** land at the chosen rectenna site. Deploy a prototype rectenna section and mass driver track segment. Validate construction techniques in lunar regolith and vacuum.

(iii) **Mass driver prototype:** build and test a 200 m sled track on the lunar surface. Launch 100 kg test masses at 1,000 m/s. Validate electromagnetic launch, sled recovery, and power systems in the lunar environment.

(iv) **Fin thermal validation:** deploy a test section of finned REBCO cable in LEO or lunar orbit. Verify that 24 carbon-fiber radiating fins with OSR coating maintain the cable below $T_c = 93$ K through the full range of solar angles. Measure coating degradation rate under UV and micrometeorite exposure.

13.5 Phase 4: Full-Scale Construction (Years 10–21, $25B)

The 11-year construction timeline from Section 11, executed after all subsystems are validated:

(i) Redirect tether asteroid (5 Mt) to L1 + 5,000 km

(ii) Redirect mining asteroid (120+ Mt) to nearby L1 orbit

(iii) Ship winding machine and cable spools to L1

(iv) Wind and deploy 62,000 km cable (5.9 years)

(v) Build surface rectenna, smelter, and mass driver

(vi) Commission ring production, begin operations

13.6 Development Timeline Summary

Phase	**Years**	**Duration**	**Cost ($B)**
0: Ground demos	0–3	3 years	0.5
1: LEO experiments	3–6	3 years	2.0
2: Asteroid technology	3–10	7 years	3.0
3: Lunar surface	6–10	4 years	2.0
4: Full-scale construction	10–21	11 years	25.0
Total	0–21	21 years	∼40

Phases 1, 2, and 3 run in parallel. The critical path is asteroid technology development (Phase 2), which must produce a validated mining capability before full-scale construction begins. Total program: ∼21 years from first ground demo to first gigawatt, at ∼$40B total investment.

For comparison, the US nuclear power industry took 22 years from the first experimental reactor (EBR-I, 1951) to the first commercial gigawatt plant (Zion Unit 1, 1973), at an inflation-adjusted cost of ∼$30B in cumulative R&D and construction. The gravity power plant follows a comparable development arc for a comparable investment.

14. Scaling to Higher Power

The plant's power output scales linearly with throughput:

Power (GW)	Throughput (t/hr)	Cable diameter	Estimated cost ($B)
0.1	133	10 mm	∼15
1.2	**1,600**	**22 mm**	**∼40 (baseline)**
5	6,667	35 mm	∼80
10	13,333	45 mm	∼120

Cable mass scales roughly as the square of diameter; cable cost scales similarly. But all other infrastructure (tether asteroid, mass driver, terminal, L1 station) is shared. The marginal cost of additional power is dominated by cable material and launch—both of which exhibit economies of scale.

At 10 GW, the gravity plant costs ∼$120B. The nuclear equivalent (100 reactors, each with 10,000 m^2 of radiators) would cost ∼$500–700B if it could be built at all.

15. From Power Plant to Colony Builder

15.1 The 1.2 GW Baseline

The initial system generates 1.2 GW from 1,600 t/hr of asteroid descent on a 22 mm cable. Iron rings are 6–12 tons each (sized to the flux-pinning capacity of the 22 mm cable), produced every 10–22 seconds by 6 parallel sintering presses at the L1 station. Of the 1.2 GW, 165 MW powers L1 orbital operations (ring production, centrifuge smelter, mining) and 1,035 MW feeds the microwave transmitter, delivering ∼725 MW to the lunar surface for the smelter, mass driver, and base operations.

15.2 First Habitat: Construction at the Tether

The first habitat is built *at the tether asteroid position* (5,000 km above L1), not in lunar orbit. This is the simplest possible construction site:

- **Material delivery:** steel from the L1 centrifuge smelter is pushed up 5,000 km of bare carbon-fiber tether. The effective gravity above L1 opposes the motion but is tiny (0.000408 m/s^2). A push of ∼64 m/s sends material coasting up to the construction site, arriving at ∼0 m/s. A small electromagnetic sled on the CF tether section handles this. No mass driver. No catching at orbital velocity.
- **Counterweight transition:** the tether asteroid provides the initial counterweight. As the habitat grows around it, the habitat's mass gradually *replaces* the asteroid as the counterweight. By completion (417 Mt), the habitat IS the tether. The asteroid is consumed or enveloped.

- **Debugging:** this is the first habitat ever built in space. Every construction technique—smelting, welding, pressure vessel assembly, life support installation—is proven here, 5,000 km from the L1 station where logistics are trivial. Failures are fixable. Lessons learned apply to all subsequent habitats.
- **Permanent lunar colony:** this habitat stays. It is the permanent lunar settlement and the permanent cable counterweight. Population: 200,000. It never departs for Mars.

No surface infrastructure is needed for the first habitat. No mass driver, no surface smelter, no rectenna. The entire construction is orbital: iron rings descend the cable (power), iron is smelted at L1 (steel), steel is pushed up the tether (delivery), habitat is assembled at the tether (construction). The surface receives nothing until colonists need ground-based power.

15.3 Phase 2: Surface Infrastructure and Mars Habitats

Once the first habitat is complete and construction techniques are proven, the system scales to Mars-bound habitat production:

1. **Build surface infrastructure:** deploy the rectenna (1.8 km), surface smelter, and mass driver—powered by the now-operational 1.2 GW gravity plant via microwave beam.
2. **Scale to 10 GW:** thicken the cable to 45 mm for the throughput needed to build habitats every ∼3 years.
3. **Place a seed keel in lunar orbit:** a ∼1 Mt structural framework, the minimum needed to host an electromagnetic catcher.
4. **The mass driver does everything else:** steel sections launched from the surface are caught by the seed keel. Each catch simultaneously *builds* the habitat and *accelerates* it out of lunar orbit (Section 15.7.1). The habitat is not built in orbit then launched—it is built *by* launching. 90% of the departure Δv is gained in the first 10× of mass growth (while the habitat is still a light framework). By completion at ∼417 Mt, the habitat is fully built AND on its Mars trajectory.

The surface mass driver is needed only for Mars-bound habitats—the first (permanent lunar) habitat was built entirely without it, at the tether position.

15.4 The 10 GW Colony Builder

At 10 GW (45 mm cable, ∼$120B), the system descends ∼13,000 t/hr through the cable. The thicker cable supports larger rings: 50-ton iron rings (170 mm bore, 2.16 m outer diameter,

3 m tall), produced every 14 seconds by 14 parallel sintering presses. The larger bore contact area of the 45 mm cable provides 4× pinning margin and 10× tilt stability for the heavier rings.

Roughly half the mining asteroid's output is sintered into rings for power generation; the other half is smelted directly at the L1 centrifuge smelter for orbital steel construction (slag repurposed as habitat radiation shielding). With 4 GW allocated to orbital smelting, the annual output is ∼40 million tons of structural steel—produced from already-metallic feedstock (no oxide reduction required), smelted in the L1 centrifuge ($1g$ at the crucible for slag separation and casting).

15.4.1 Habitat sizing: spin loads and wall design

A spinning habitat has two sources of hoop stress: internal air pressure ($\sigma_p = Pr/t$) and the wall's own centrifugal weight ($\sigma_w = \rho g r$, independent of wall thickness). For steel ($\rho = 7{,}800$ kg/m^3) at $1g$ and 500 m radius, the self-weight stress alone is 38 MPa—15% of steel's working stress. At 3,200 m radius (O'Neill's Island Three), self-weight stress reaches 245 MPa—98% of steel's strength, with zero margin for air pressure. **Steel cannot build Island Three at any wall thickness.**

The self-weight stress $\sigma_w = \rho\omega^2 r^2 = \rho g r$ applies to *each individual fiber* of wall material, regardless of whether the wall is solid plate or an open truss. A truss reduces the wall's average density but does not reduce the stress in each fiber—every steel fiber has density 7,800 kg/m^3 regardless of arrangement. What the truss does is allow the use of *higher-strength* material: cold-drawn wire at 900 MPa instead of as-cast plate at 250 MPa. The self-weight stress is the same; the stress budget is 3.6× larger.

For a 2 km habitat ($r = 1{,}000$ m) with cold-drawn asteroid iron-nickel wire ($\sigma_{\text{allow}} = 600$ MPa at SF = 1.5):

$$\sigma_w = \rho \cdot g \cdot r = 7{,}800 \times 9.81 \times 1{,}000 = 76.5 \text{ MPa} \quad (12.8\% \text{ of budget}) \tag{24}$$

This leaves 523.5 MPa (87.2%) available for atmospheric pressure, interior mass, and shielding loads. The habitat does not fly apart—but the self-weight consumes a non-trivial fraction of the strength:

Diameter	σ_w (MPa)	% of 600 MPa	Available	Verdict
0.5 km	19	3.2%	96.8%	comfortable
1 km	38	6.4%	93.6%	comfortable
2 km	77	12.8%	87.2%	comfortable
3 km	115	19.1%	80.9%	comfortable
4 km	153	25.5%	74.5%	workable
6.4 km	245	40.8%	59.2%	tight

With 250 MPa solid plate, the 2 km habitat is impossible (self-weight = 31%, but the plate must also carry all loads—no margin). With 900 MPa cable, the same habitat is comfortable. Island Three (6.4 km) is tight but structurally feasible—41% for self-weight, 59% for loads. The truss/cable approach does not reduce self-weight; it provides the stress budget to tolerate it.

Basalt fiber: available from day one. The lunar regolith *is* basalt. Melting it at 1,400°C (the smelter already operates at this temperature) and drawing fibers produces basalt fiber: σ = 3,000–4,800 MPa, ρ = 2,700 kg/m^3, specific strength 1,500 MYuri—**13× better than cold-drawn steel wire**. No imports, no chemistry, no waiting for industrial maturity. Add a fiber-drawing station to the existing smelter.

With basalt fiber hoop cables at 2 km diameter: self-weight stress drops to 26.5 MPa (1.3% of budget). Structural mass drops from ∼134 Mt to ∼12 Mt—an 11× reduction. The habitat wall becomes basalt fiber hoop cables (from regolith) + steel skins (from asteroid) + raw iron shielding (from asteroid). Each material does what it is best at: basalt carries the tension, steel seals the atmosphere, iron stops the radiation.

Cable material	σ (MPa)	ρ (kg/m^3)	Sp. str.	Struct. mass	Source
Steel wire (cold-drawn)	900	7,800	115	134 Mt	M-type asteroid
Basalt fiber	**3,000**	**2,700**	**1,500**	**12 Mt**	**Lunar regolith**
Carbon fiber	7,000	1,800	3,889	7 Mt	C-type (complex chemistry)

First-generation habitats may use steel wire (proven, available from the asteroid). But basalt fiber is producible from regolith using existing smelter infrastructure, and its 13× specific strength advantage makes it the preferred hoop cable material as soon as fiber-drawing capability is established—likely within the first years of gravity plant operation.

The habitat wall is a 2 m deep truss-and-cable sandwich:

(i) **Outer skin** (5 mm steel): gas-tight membrane, first impact layer.

(ii) **Outer 1 m: raw asteroid rock** (unprocessed iron-nickel chunks packed between truss members). This is the radiation shield (750 g/cm^2 at ρ = 7,500 kg/m^3) and micrometeorite armor (1 m of iron stops everything <20 cm). **This rock is not smelted**—it is packed raw, directly from the asteroid.

(iii) **Inner 1 m: utilities space** (pipes, wiring, water tanks, access corridors). Water tanks here add ∼50–100 g/cm^2 of additional radiation shielding.

(iv) **Inner skin** (5 mm steel): interior surface.

(v) **Hoop cables** (cold-drawn asteroid iron-nickel wire, 800–1,000 MPa): woven through the truss, carrying all hoop tension. Cold-drawn wire is 3–4× stronger per kilogram than as-cast plate—same asteroid metal, processed through dies. This is 3,000-year-old metallurgy.

(vi) **Truss members** (steel tubes at ∼10% fill factor): provide stiffness and carry shear loads. Effective density ∼800 kg/m^3 vs. 7,800 for solid steel, reducing self-weight stress from 38 MPa to ∼4 MPa.

15.4.2 Radiation and impact protection

In space outside Earth's magnetosphere, galactic cosmic rays (GCR) deliver 600–1,000 mSv/year unshielded—1,000× the public exposure limit. The 1 m iron shielding layer provides 750 g/cm^2 of mass depth:

- GCR reduction: ∼95%. Residual dose: 30–50 mSv/year (within radiation worker limits of 50 mSv/year).
- Water tanks in the inner wall add 50–100 g/cm^2, reducing the dose to 20–35 mSv/year.
- Solar particle events (SPE): the 1 m iron wall provides complete protection against all but the most extreme events.
- Micrometeorites: 1 m of iron stops all particles <20 cm diameter. The habitat is essentially immune to micrometeorite puncture—far superior to Whipple shielding.

15.4.3 Mass budget per habitat

For the 2 km reference habitat:

Component	Processing	Mass (Mt)
Hoop cables (steel wire)	Smelted + drawn	101
or: Hoop cables (basalt fiber)	*Melted + drawn from regolith*	*9*
Skins (2 × 5 mm steel)	Smelted + rolled	3
Truss framework	Smelted + formed	30
Total structural (steel cables)		**134**
Total structural (basalt cables)		**42**
Radiation shielding (1 m iron chunks)	**Unprocessed**	283
Total per habitat (steel / basalt)		**417 / 325**

With steel cables, 32% requires smelting. With basalt fiber cables (from regolith), only 10% of the asteroid mass requires smelting—the rest is raw shielding. Nature made the shielding 4.5 billion years ago; the robots just pack it into the walls.

15.4.4 The reference habitat: 2 km diameter

Scaling from 1 km to 2 km diameter yields 4× the living area at roughly the same mass per capita, with a lower, more comfortable spin rate (0.9 RPM vs. 1.3). The 2 km habitat is the practical sweet spot:

Parameter	Value
Dimensions	2 km diameter × 5 km length
Interior surface area	31 km^2
Artificial gravity	1g at 0.9 RPM
Population (mid-rise)	∼200,000
Structural mass (smelted)	134 Mt
Shielding mass (raw rock)	283 Mt
Total	417 Mt
Wall self-weight stress	76.5 MPa (12.8% of cable budget)
Build time at 10 GW	∼3 years

15.4.5 One asteroid, one city

A single 600 m M-type asteroid (565 Mt raw) provides the full 417 Mt needed for one 2 km habitat: 134 Mt smelted into structural cable and skin, 283 Mt packed raw as radiation shielding, with material to spare. There are an estimated 100–200 M-type NEAs of this size in the near-Earth population.

One 600 m asteroid = one city for 200,000 people.

At 10 GW plant output, one habitat every ∼3 years. At 100 GW, one every ∼4 months. A 1 km M-type asteroid (2,618 Mt) yields 6–7 habitats housing over 1 million people.

15.4.6 Spin-up sequence

The habitat is spun up *before* adding interior mass and shielding. The empty structural shell at 0.9 RPM experiences only the self-weight stress of the cables and truss (∼4 MPa, 0.7% of cable strength). Interior mass and shielding are added gradually while spinning—like filling a swimming pool. The loads increase smoothly and predictably. If the structural monitoring detects excessive stress, loading stops. The system is inherently self-limiting.

15.4.7 Lunar regolith: completing the bill of materials

The asteroid provides iron-nickel for structure and shielding. But a habitat needs more than steel. The gravity plant sits on the lunar surface with ∼1 GW of power and unlimited regolith outside the door. The same smelter complex that processes asteroid material can process lunar regolith into everything the habitats need that iron-nickel does not provide:

Product	**Source mineral in regolith**	**Regolith fraction**
Oxygen (atmosphere)	all silicates and oxides	40% by mass
Silicon (solar cells, electronics)	SiO_2 (silica)	21%
Aluminum (structures, wiring)	Al_2O_3 (alumina)	8%
Glass (windows, fiber optics)	SiO_2 + fluxes	21%
Titanium (high-strength parts)	$FeTiO_3$ (ilmenite)	1–5%
Calcium (cement, ceramics)	CaO (lime)	9%
Magnesium (alloys)	MgO (magnesia)	6%

The asteroid provides the steel skeleton and radiation armor. The Moon provides glass, aluminum, titanium, oxygen, and ceramics. The gravity plant powers both processing chains with the same 1 GW. The habitats receive a complete bill of materials from two sources—**zero from Earth** after initial construction.

This is the second half of the bootstrapping solution: the asteroid solves the steel and energy problem, the Moon solves the materials-diversity problem. Neither alone is sufficient; together they provide everything a self-sustaining habitat needs.

15.4.8 Habitat power and lighting

The habitat is a sealed steel cylinder with 1 m of iron shielding—no windows. All light is artificial. All power comes from solar panels on the exterior surface.

Power source: thin-film silicon solar panels manufactured from lunar regolith (SiO_2 is 21% of regolith). The habitat has 38 km^2 of exterior surface. Covering 25% with panels at 20% conversion efficiency in lunar orbit (1,360 W/m^2):

$$P_{\text{solar}} = 0.25 \times 38 \times 10^6 \times 1{,}360 \times 0.20 = 2{,}584 \text{ MW} \approx 2.6 \text{ GW} \tag{25}$$

At Mars (590 W/m^2, 43% of Earth): covering 50% of the surface yields 2.3 GW—still adequate.

Power budget:

System	**Power (MW)**
Agriculture lighting (9 km^2 LED grow lights at 200 W/m^2)	1,800
Residential and commercial lighting	200
Life support (air recycling, water, thermal control)	50
Industry, transport, communications	200
Total demand	**∼2,250**
Solar supply	**∼2,600**
Margin	15%

Lighting: LED grow lights for agriculture are more efficient than sunlight for photosynthesis—optimized red + blue spectrum delivers 40% more photosynthetically active radiation per watt than broadband solar. The programmable day/night cycle (any desired duration) eliminates seasons, weather, and clouds. Residential lighting simulates a natural diurnal cycle.

During lunar eclipses (∼45 minutes per 2-hour orbit), battery storage maintains critical systems. The eclipse fraction is <4% of orbit time.

The solar panels, LED fixtures, and batteries are manufactured from the same lunar regolith pipeline that provides the habitat's glass, aluminum, and oxygen. The habitat's power system is fully bootstrapped—no Earth imports required.

15.4.9 Water, nitrogen, and volatiles: C-type asteroids

The M-type asteroid provides iron-nickel (structure and shielding) but no water, nitrogen, or carbon. The Moon provides oxygen but is essentially dry. The habitat's atmosphere (19 Mt of air, 78% nitrogen) and water supply (∼2 Mt) must come from a third source:

C-type (carbonaceous) asteroids, the most common NEA type (∼75% of all near-Earth asteroids).

Resource	C-type fraction	Per 1 km C-type	Habitat needs
Water (hydrated minerals)	10–20%	80–160 Mt	∼2 Mt
Nitrogen (organics, NH_3)	2–4%	16–31 Mt	∼15 Mt
Carbon (organics, CO_2)	3–5%	24–39 Mt	∼5 Mt

One 1 km C-type asteroid (785 Mt) provides all the volatiles for a single habitat. Several 300 m C-types serve equivalently.

Processing requires no trip to the lunar surface. Unlike M-type steel processing (which requires lunar gravity for smelting, slag separation, and casting), C-type volatile extraction is simply *heating rock*: water, nitrogen, and carbon compounds boil off at 200–600°C. No gravity required. The habitat processes C-type material in orbit using its own 2.6 GW of solar power:

(i) Catch or ferry C-type chunks to the habitat

(ii) Heat in a solar furnace or electric oven (>400°C)

(iii) Collect outgassing: steam → condense to liquid water; NH_3/N_2 → atmosphere; CO_2/hydrocarbons → agriculture feedstock

(iv) Dry residue (silicates) → additional shielding or discard

This makes the habitat *partially self-sufficient from day one*. Structural steel requires the lunar gravity plant. Volatiles do not—the habitat processes them independently in orbit.

15.4.10 Complete bill of materials

Source	Provides	Size needed	Processing
M-type asteroid	Steel structure + shielding	1 × 600 m	Lunar surface smelter
C-type asteroid	Water + nitrogen + carbon	1 × 1 km	In-orbit solar heating
Lunar regolith	O_2, Si, Al, glass, Ti, ceramics	Unlimited	Lunar surface processing

Three in-space sources provide all bulk materials. However, one critical category **must still come from Earth**:

Source	Provides	Volume	Duration
Earth	Robots (Optimus-class), electronics, semiconductors, AI chips, sensors, specialty chemicals, biological materials (seeds, cultures, medical)	A few Starship flights per year	Until local semiconductor fabrication is mature (decades)

These are low-mass, high-value items—a few Starship flights per year, not hundreds. The gravity plant eliminates Earth dependency for bulk materials (steel, fuel, shielding, water, air, soil). Robots and electronics are the last Earth dependency and the hardest to replace with local manufacturing. Semiconductor fabrication from lunar silicon is theoretically possible but requires an industrial sophistication that will take decades to develop off-Earth. Until then, every habitat needs a steady supply of robots from Earth to build, maintain, and operate the system.

A Mars-orbit habitat can eventually source C-type volatiles locally—Phobos and Deimos may be captured C-type asteroids, providing water, nitrogen, and carbon without any connection to the Earth-Moon system. But it will still need robots and electronics from Earth for the foreseeable future.

15.4.11 Lunar vicinity, not Earth orbit

The first habitat is at the tether position (5,000 km above L1); subsequent habitats are built in lunar orbit. Neither is in Earth orbit. This is not merely a convenience of logistics. A 2 km habitat is 400 million tons of steel and iron spinning at 0.9 RPM. In Earth orbit, any orbital decay terminates in the atmosphere—a catastrophic impact event. In lunar orbit, a failure drops the structure onto an uninhabited surface. The consequences are tragic for the residents and irrelevant to Earth. Placing the largest structures ever built in orbit around the body with no biosphere is not optional; it is the only responsible engineering choice.

15.5 Why This Is the Only Practical Path

The gravity power plant solves the O'Neill bootstrapping problem because it provides all three requirements simultaneously from a single system:

1. **Power** (10 GW)—from gravity acting on asteroid rock. No nuclear fuel, no radiators, no solar intermittency. The fuel is free and the generator has zero moving parts.

2. **Material** (120 Mt/year of iron-nickel)—the same rock that generates the power. Already metallic (M-type asteroid), requiring only melting, not oxide reduction. Saves $\sim$14,000 MJ/ton compared to lunar regolith processing.

3. **Industrial gravity**—the L1 centrifuge smelter provides $1g$ at the crucible via a rotating arm. Slag separates, convection works, metal can be cast and rolled. The first habitat at the tether provides $\frac{1}{6}g$–$1g$ (depending on spin-up stage) for additional manufacturing.

No other proposed system provides all three. Solar provides power but not material. Asteroid mining provides material but not gravity for processing. Nuclear provides power but requires an Earth-dependent fuel supply chain that cannot scale. Only the gravity power plant bootstraps from Earth-delivered components (cable and ring production equipment) to a fully self-sustaining industrial base.

15.6 The Uranium Argument

Earth's continental crust is the solar system's only concentrated source of uranium—a thin film of incompatible elements pushed to the surface by 4.5 billion years of plate tectonics and hydrothermal concentration. No other body has plate tectonics. No other body has liquid water. Lunar uranium is 100× more dilute than Earth's crust; asteroid uranium is 10,000× more dilute. Nuclear power anywhere except Earth requires *permanently* importing fuel from the one planet that has it. The gravity power plant's fuel is the most common solid material in the solar system: iron-nickel rock.

15.7 A Shipyard for the Solar System

The first habitat is built at the tether position (no mass driver needed). Subsequent Mars-bound habitats are built in lunar orbit, where the surface mass driver delivers structural steel. But these need not stay at the Moon.

15.7.1 Departure: construction steel as propulsion

During construction in lunar orbit, the mass driver launches steel at 2,165 m/s—slightly faster than the 1,680 m/s needed for orbit. Each piece arrives with excess velocity that the habitat absorbs as momentum. As the habitat speeds up, the relative velocity of incoming steel *decreases* (the steel is launched at a fixed speed from the surface). The correct physics gives a maximum delta-v of ∼440 m/s from a 2,165 m/s surface mass driver—enough to depart lunar orbit onto a slow interplanetary trajectory, but not enough for a fast Mars transfer.

This is sufficient. The habitat does not need a fast transfer. It needs a *slow* one.

15.7.2 The 10-year slow transfer

A Hohmann transfer to Mars takes 9 months and requires ∼1,500 m/s of delta-v—too much for the surface mass driver alone. But the habitat is a permanent structure. It does not care whether the trip takes 9 months or 10 years. A slow trajectory using gravitational assists from the Earth, Moon, and Sun can reach Mars with total delta-v of 200–400 m/s, well within the 440 m/s the surface mass driver provides for free during construction.

The travel time is the construction time: autonomous robots (Optimus-class humanoid units) complete the interior fit-out, install life support, spin the habitat up to 1.3 RPM for artificial gravity, and commission all systems during the multi-year coast. The habitat arrives at Mars fully built, tested, and ready for occupancy.

Zero propellant is expended for the departure. The construction steel provides the push. Every kilogram is structure; none is wasted as reaction mass.

15.7.3 Arrival: flip the habitat, catch slingshot steel

No infrastructure is needed at Mars before the habitat arrives. The habitat carries its own braking system—the same electromagnetic catcher used during construction in lunar orbit. The braking fuel is steel launched from the Moon, slingshot around Mars by gravity assist, and caught by the habitat from the front.

The sequence:

1. **Months before arrival,** the lunar mass driver launches steel slugs on trajectories aimed at Mars. These slugs travel ahead of the habitat.

2. **Each slug slingshots around Mars** via gravitational assist. At low approach velocities (<1 km/s), Mars provides 90–120° of trajectory deflection with closest approach of 3,000–15,000 km above the surface—well-understood orbital mechanics (Voyager, Cassini, etc.). The slug exits the slingshot heading *back toward the approaching habitat.*

3. **The habitat flips 180°** so its electromagnetic catcher faces forward (toward Mars). The habitat is a spinning cylinder—rotation about a perpendicular axis is a straightforward attitude maneuver.

4. **The habitat catches each returning slug.** The catcher decelerates the slug over its 500 m electromagnetic track. Each catch transfers momentum: the habitat slows, the slug becomes part of the habitat.

Zero propellant is expended. Every slug caught becomes radiation shielding, soil, or construction material inside the habitat. Nothing is thrown away. The braking fuel *becomes part of the habitat.*

The arrival speed is a design choice. Arriving faster means catching more slugs, which means more radiation shielding. Arriving slower means less braking, less shielding. The designer tunes the approach velocity to match the desired shielding mass:

Approach speed	Slugs caught	Braking months	Shielding mass
5 m/s	∼1 Mt	∼1	thin
25 m/s	∼5 Mt	∼3	moderate
50 m/s	∼10 Mt	∼6	∼1 m of hull coverage

Mars orbit has significant radiation exposure (no planetary magnetosphere). A 50 m/s approach provides ∼10 Mt of shielding—adequate for permanent habitation—while still requiring only months of gentle braking at imperceptible deceleration.

No Phobos mass driver required. No Mars infrastructure of any kind. The first habitat arrives at Mars using only the lunar mass driver (for slug launch), Mars's gravity (for the slingshot), and the habitat's own catcher (already built for construction). The Moon builds, launches, and brakes—Mars just provides the gravity assist.

15.7.4 The complete Mars delivery sequence

Year	Milestone
0	1 Mt seed structure assembled in lunar orbit
0–0.6	Mass driver launches steel at 2,165 m/s. Habitat catches, builds, gains 440 m/s. Construction is propulsion.
0.6	Habitat complete (22 Mt), departing lunar orbit
0.6–1	Gravitational assists from Earth/Moon boost to Mars-crossing trajectory
1–10	Slow coast. Interior fit-out. Spin up to 1.3 RPM. Systems commissioning.
8–10	Lunar mass driver launches steel slugs on Mars-slingshot trajectories.
9.5	Approach Mars. Habitat flips 180°. Catcher faces forward.
9.5–10	Months of gentle braking. Slingshot slugs caught = radiation shielding.
10	Habitat enters Mars orbit. Residents arrive via Starship.

Total propellant expended: zero. At departure, the construction steel is the propulsion. At arrival, the braking regolith is the shielding. Every kilogram serves double duty. Nothing is wasted.

15.7.5 Mass budget from one 500 m asteroid

A single 600 m asteroid (565 Mt raw) provides the complete material for one 2 km habitat: 119 Mt smelted structural steel + 283 Mt raw shielding = 401 Mt total, with ∼160 Mt of material remaining for a second partial habitat or for export. A 1 km asteroid (2,618 Mt) builds 6–7 complete habitats.

For the Mars-bound habitat, the construction steel provides departure propulsion (440 m/s from the mass driver) and the slingshot braking slugs become interior shielding at Mars. **Zero propellant expended. Every kilogram is structure or shielding.**

15.7.6 No Mars infrastructure required

Unlike every other Mars colonization proposal, this architecture requires *zero pre-positioned infrastructure at Mars.* No Phobos mass driver. No fuel depots. No orbital stations. The first habitat arrives using only three things: the lunar mass driver (at the Moon), Mars's gravity (for the slingshot), and the habitat's own catcher (built during construction). The Moon does all the work. Mars just shows up.

15.7.7 The robot fleet

Each habitat carries ∼8,000 autonomous robots (Optimus-class humanoid units) that build the city during the 10-year transit. The fleet is sized by the construction workload:

Task	**Robots**	**Work**
Welding (structure assembly)	1,200	Catch steel sections, weld into structure (7-month blitz)
Shielding (pack raw chunks)	1,600	Load iron-nickel chunks into wall cavities
Interior construction	3,600	Floors, walls, plumbing, wiring, HVAC
Agriculture	1,000	LED arrays, hydroponics, soil beds, planting
Specialized systems	500	Life support, water treatment, electrical, commissioning
Total	**∼8,000**	

At 70 kg each: 554 tons total. Six Starship flights. ∼$400M at mass-production pricing. The robot fleet is the cheapest, lightest component of the habitat—a rounding error in the mass and cost budgets.

Working 24/7 for 10 years, 8,000 robots are equivalent to ∼24,000 human construction workers on three shifts—a normal workforce for building a city of 200,000 on Earth. The robots are the last item that must come from Earth: semiconductors, sensors, and AI chips cannot yet be manufactured from asteroid iron and lunar regolith. A few Starship flights per year of robots and electronics are the system's final Earth dependency.

15.7.8 Timeline: one million at Mars

Starting construction in 2026:

Year	**Milestone**
2026–2047	Gravity plant development and construction (21 years)
2047	Plant operational at 1 GW. Begin scaling to 10 GW.
2047–2050	**First habitat built in lunar orbit** (proof of concept, commissioning, first residents)
2050	Second habitat: 1 Mt seed keel enters lunar orbit. Mass driver begins launching steel—every catch simultaneously builds the structure, packs shielding, and provides propulsion. Construction IS the transit: the habitat is complete when the last steel section is caught, at which point it is also on its Mars trajectory. Interior fit-out (atmosphere, agriculture, systems) continues during the remaining coast.
2053	Third habitat shell launched; robots building second en route
2056	Fourth launched; second nearing completion in transit
2059	Fifth launched; pipeline fully loaded
2060	**First habitat arrives at Mars orbit** (10-year transit). 200,000 capacity.
2063	Second habitat arrives at Mars
2066	Third habitat arrives
2069	Fourth habitat arrives
∼2070	**Five habitats in Mars orbit. One million people.**

For comparison, conventional Mars colonization using Starship-to-surface requires launching every person, every supply, and every building component from Earth on chemical rockets. Mars transfer windows open every 26 months. Even at 100 Starships per window (10,000

people), reaching one million takes over 200 years. Residents live in pressurized tunnels at $0.38g$—no confirmed long-term health outcomes, limited radiation shielding, limited agriculture, permanent dependence on Earth resupply.

The gravity plant approach ships *cities*, not people. Each habitat is a self-sufficient 31 km^2 city at full $1g$ gravity, radiation-safe, impact-proof, with closed-loop agriculture—assembled during transit by autonomous robots, arriving at Mars ready for occupancy. Residents travel to their new city via Starship after it is in Mars orbit. Zero propellant is expended to deliver the habitat. One million people in five cities, orbiting Mars, by 2070.

15.7.9 Self-replicating architecture

The habitat that arrives at Mars is not merely a city. It is an *industrial seed* that replicates the gravity power plant architecture at its destination—including the superconducting cable, manufactured entirely from local materials.

Why REBCO enables self-replication. Previous superconductor candidates required permanent Earth dependency. MgB_2 needs boron (5 ppm in regolith—extractable but energy-intensive). Bi-2223 needs bismuth (10 ppb—essentially absent off-Earth) and 31,000 tons of silver per cable. REBCO's thin-film architecture changes this equation: the superconductor layer is only ∼19 tons of $YBa_2Cu_3O_7$ on ∼62,000 tons of Hastelloy substrate (Ni/Cr/Fe/Mo). Every element is present in M-type asteroid smelting residues at concentrations that yield adequate tonnage from the gravity plant's 120 Mt/year throughput:

Element	**Asteroid (ppm)**	**Yield (t/yr)**	**Need (tons)**	**Surplus?**
Nickel (substrate)	50,000–100,000	6–12 Mt	35,300	$\gg 100\times$
Chromium (substrate)	3,000	360,000	9,900	$36\times$
Iron (substrate)	850,000+	102 Mt	3,100	$\gg 100\times$
Molybdenum (substrate)	5–10	600–1,200	9,900	marginal
Copper (REBCO)	100–500	12,000–60,000	5.4	$\gg 100\times$
Yttrium (REBCO)	0.1	12	2.5	$5\times$
Barium (REBCO)	0.01	1.2	7.7	accumulate 6 yr
Oxygen (REBCO)	from regolith	unlimited	3.2	unlimited

The PLD manufacturing process works in vacuum (free at any orbital facility) with only trace O_2 (from local oxide minerals). The REBCO targets are fabricated from accumulated trace elements. The Hastelloy substrate is continuously cast and rolled from refined asteroid alloy. **No element in the cable requires import from Earth.**

The Mars gravity plant uses the same single-cable + microwave architecture as the Moon, and is simpler because of Mars's atmosphere.

Single-cable architecture. One cable hangs from areostationary orbit (the habitat at 401 Mt is the counterweight) to 100 km altitude, where the atmosphere begins. The REBCO superconductor ends at 100 km. Iron rings fall off into the atmosphere. Power is beamed to the surface via a 1 km microwave phased array at the habitat—Mars's thin CO_2 atmosphere (6 mbar) is transparent at 5.8 GHz. No cable passes through the atmosphere. No surface anchor. No atmospheric thermal problem.

Iron rings—identical to the lunar design. 10-ton sintered iron half-rings, resistance-welded and magnetized with a 10 kA pulse, clamped around the Drop Cable. Flux pinning engages. Rings descend 16,932 km from areostationary to the 100 km cable endpoint, generating power via Lenz's law braking. At the endpoint, REBCO ends, flux pinning vanishes, the ring falls off.

Pendulum sweep. The free-hanging Drop Cable swings exactly as on the Moon: deflection kick reaction, ring imbalance vibration, and the natural pendulum period (different from the lunar 16 days due to the shorter 17,032 km cable and Mars gravity gradient) combine to sweep the impact zone across a km-scale area on the surface. A deflection coil at the cable endpoint offsets each falling ring from directly below the cable, keeping the dust plume away from the REBCO. The sweeping impact zone provides the same benefits as on the Moon: distributed quarry, inherent vehicle safety, no single point of repeated impact.

Iron rain through the atmosphere. The rings fall 100 km through the thin Martian atmosphere (6 mbar surface pressure). Starting from $\sim$0 m/s, they free-fall to $\sim$860 m/s at the surface—well below terminal velocity in the thin atmosphere. Aerodynamic heating raises their temperature by only $\sim$7 K. They do not melt. Impact creates craters 5–10 m across. The iron rain is simultaneously **power generation** (during descent), **excavation** (impact digs the crater), and **ore delivery** (iron lands in the hole it dug). Autonomous surface vehicles trail the sweeping impact zone, collecting iron and delivering it to the smelter.

M-type asteroids from the belt. Mars orbits at 1.52 AU—roughly half the distance to the asteroid belt (2.2–3.2 AU) compared to Earth. The ΔV to redirect an M-type asteroid from the belt to Mars is $\sim$2–3 km/s, versus $\sim$5–6 km/s to the Earth-Moon system. Mars is the natural destination for belt asteroids. The same solar electric tugs used for the lunar

program redirect M-type asteroids to Mars areostationary orbit, providing already-metallic iron-nickel feedstock identical to the lunar design. Phobos (likely C-type, iron locked in silicates) is reserved for its volatiles—water, carbon, nitrogen for habitat life support—not used as an inefficient iron source.

The replication sequence.

1. **Arrive at Mars.** The habitat (401 Mt) enters areostationary orbit. It has spent 10 years being built and commissioned during transit. The habitat itself is the cable counterweight.

2. **Deploy one cable.** The habitat's onboard PLD facility manufactures REBCO tape from stockpiled asteroid-refined metals and deposits it onto a single cable lowered toward Mars—free-hanging, ending at 100 km altitude (above the atmosphere). The reduced solar flux at Mars (589 W/m^2) keeps the REBCO cable at $\sim$56 K with 24 fins—37 K margin below T_c. Power is beamed to the surface via a 1 km microwave array at the habitat.

3. **Redirect a belt asteroid.** A solar electric tug redirects a small M-type asteroid ($\sim$120 Mt) to the vicinity of areostationary orbit. The lower ΔV from the belt to Mars (vs. belt to Earth) makes this easier than the lunar program's asteroid redirect.

4. **Begin operations.** Iron-nickel from the asteroid is crushed, sintered into rings, and loaded onto the cable. Rings descend, generating power ($\sim$9.2 MJ/kg gravitational PE from areostationary to 100 km—3.4$\times$ the lunar value due to Mars's deeper gravity well). At 400 t/hr throughput: $\sim$1 GW. Power is extracted at the habitat SMES and beamed to the surface via microwave.

5. **Iron rain and surface smelting.** Rings fall from 100 km, impacting the surface in the sweeping quarry zone. Autonomous vehicles trail the moving impact point, collecting iron. The smelter, powered by the gravity plant, produces structural steel for Mars surface infrastructure. Mars now has GW-scale continuous power and a self-filling iron mine—independent of sunlight, dust storms, or Earth resupply.

6. **Build the next generation.** The Mars gravity plant manufactures new REBCO cables from asteroid trace elements (Y, Ba, Cu from smelting residues; Hastelloy substrate from Ni/Cr/Fe/Mo). New habitats are built, launched toward Jupiter and Saturn—each carrying PLD equipment and the capability to replicate the architecture at the next destination.

Every gas giant has dozens of moons. Every moon is a potential counterweight and material source. Every gravity well is a power source. The architecture works everywhere there is mass above a surface—which is everywhere in the solar system.

The lunar gravity plant is not a power plant. It is the first node in a *self-replicating industrial civilization* that propagates through the solar system using gravity as its energy source and local asteroids as its material source. The Moon builds the first generation. Each habitat builds the next. The only thing that must ever come from Earth is the initial cable materials and PLD equipment—40 billion dollars of carbon fiber, Hastelloy, and manufacturing tools. Everything after that—including the superconducting cable itself—comes from rocks and gravity.

16. Conclusion

O'Neill's vision of space colonies has been waiting fifty years for someone to explain where the power and material come from. This paper proposes the answer: a superconducting cable from the lunar surface to Earth-Moon L1 that converts the gravitational potential energy of asteroid rock into electricity, while the same rock becomes the structural steel of the colonies.

The system is dominated by passive mechanisms: gravity drives the iron rings down, Lenz's law provides braking, and flux pinning locks and centers the rings on the cable. At the terminal, the superconductor simply ends—the rings release and drop. The only active components are the ring sintering press at L1, the mass driver for steel export, and the power extraction electronics.

At 1.2 GW baseline capacity, the system costs ∼\$40B—comparable to the \$50–70B required for equivalent lunar nuclear power, which faces unsolved problems of heat rejection in vacuum, enriched uranium launch risk, and supply chain dependency. At 10 GW, it produces one fully protected 2 km habitat (31 km^2, 200,000 residents, full 1g at 0.9 RPM, radiation-safe, impact-proof) every ∼3 years from a single 600 m asteroid—at a cost of ∼\$120B. The nuclear equivalent (100 reactors with 1,000,000 m^2 of radiators, permanently dependent on enriched uranium launched from Earth) would cost \$500–700B if it could be built at all.

The technology risk is real: a 62,000 km cable is a single point of failure, asteroid mining is at TRL 1, and the full system requires 21 years of development. But the physics is sound (Lenz's law, flux pinning, and gravity do not fail), the materials exist (commercial carbon fiber and REBCO superconducting tape), and the development cost (\$40B over 21 years) is comparable to what the US spent building its nuclear power industry from scratch.

What makes this architecture unique is not any single component but the way they

compose: the cable is the generator, the brake, and the battery. The iron ring is the fuel, the carrier, and the construction material. The asteroid is the feedstock, the shielding, and the counterweight. The habitat is the city, the factory, and the seed for the next gravity plant. Every element serves multiple purposes. Nothing is wasted. Nothing is thrown away. The system propagates itself from world to world using the two resources available everywhere in the solar system: rocks and gravity.

There is one final property worth noting: the system *compels* expansion. The gravity plant is powered by the rings that descend it. The ring foundry is powered by the gravity plant. Stop dropping rings, and twelve hours later the last ring falls off the cable, the power dies, and the foundry goes dark—with no way to restart. To keep the lights on, you must keep making rings. Every ring generates power AND delivers iron. The iron accumulates whether you use it or not. Building something with it is not optional—it is the only alternative to burying your civilization in its own fuel. The gravity plant does not merely *enable* an industrial civilization in space. It *requires* one.

The Moon has no coal, no oil, no rivers, and no uranium worth mining. But it sits at the bottom of a gravitational potential well with iron-nickel asteroids at the top. This paper proposes building a pipe between them—and using what comes out to seed an industrial civilization across the solar system.

References

[1] T. A. Coombs, "Superconducting flux pumps," *J. Appl. Phys.* **125**, 230902 (2019). doi:10.1063/1.5098384.

[2] M. E. Emetere, "Yttrium cuprates modification in linear generator application for power generation," *Clean Energy* **8**(5), 229–240 (2024). doi:10.1093/ce/zkae062.